

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
JUL 27 2011
KCC WICHITA

Form CP-4
March 2009
Appear or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6044
Name: Stelbar Oil Corporation, Inc.
Address 1: 1625 N. Waterfront Parkway, Suite 200
Address 2: _____
City: Wichita State: KS Zip: 67206 + _____
Contact Person: Roscoe Mendenhall
Phone: (316) 440-7605
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Keyes Sand Depth to Top: 5364' Bottom: 5370' T.D. 5370'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 187-21087 ~~29-00~~
Spot Description: _____
NE NE NW Sec. 24 Twp. 30 S. R. 41 East West
330 Feet from North / South Line of Section
2190 Feet from East / West Line of Section
GPS KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Stanton
Lease Name: Armstrong Well #: 1-24
Date Well Completed: 12/18/2006
The plugging proposal was approved on: 7/7/2011 (Date)
by: Eric Maclaren (KCC District Agent's Name)
Plugging Commenced: 7/8/2011
Plugging Completed: 7/11/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	1657'	None
		Production	5-1/2"	5580'	3230'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mix and pump 25 sacks cement and 200 lbs. hulls and displace with mud to 5000'. Shot off 5-1/2" casing at 3230' and placed cement plugs as follows: 50 sacks at 1680', 50 sacks at 600' and 10 sacks from 40' to surface. Used mud to displace cement plugs. Cut off 8-5/8" casing four feet below ground level and weld on steel cap. All cement is Portland Type 1.

Plugging Contractor License #: 32833 Name: Sargent and Lilliard Casing Pulling, Inc.
Address 1: P.O. Box 1450 Address 2: _____
City: Woodward State: Oklahoma Zip: 7382 + _____
Phone: (580) 254-1881
Name of Party Responsible for Plugging Fees: Stelbar Oil Corporation, Inc.
State of Kansas County, Sedgwick, ss.
Roscoe Mendenhall Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Roscoe Mendenhall