

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-171-20,379-0000

LEASE NAME YORK "BZ"

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER #1

4240' Ft. from S Section Line

2260' Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 31 ~~XX~~ or (W)

COUNTY Scott

Date Well Completed March 2, 1989

Plugging Commenced March 2, 1989

Plugging Completed March 2, 1989

LEASE OPERATOR SLAWSON EXPLORATION COMPANY, INC.

ADDRESS 104 South Broadway, Wichita, Kansas 67202

PHONE#(316) 263-3201 OPERATORS LICENSE NO. 3988

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 2, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filled? by operator If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4583'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface		0	310	8 5/8"	310'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

1st plug at 2280' W/50 sx, 2nd plug at 1500' W/80 sx, 3rd plug at 350' W/50 sx, 4th plug at 40' W/10 sx, 15 sx. in rathole --Total 205 sx. 60/40 pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing License No. \_\_\_\_\_

Address P. O. Box 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: SLAWSON EXPLORATION COMPANY, INC.


STATE OF KANSAS COUNTY OF BARTON, ss.

Greg Davidson (Employee of Operator) or (Owner) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 7th day of March, 1989



My Commission Expires: 5-20-89

Bessie M. DeWerff  
 Notary Public  
 Bessie M. DeWerff

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAR 08 1989  
 3-8-89  
 CONSERVATION DIVISION  
 Wichita Kansas

FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas  
NOTICE OF INTENTION TO DRILL

171-20,319-0000  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... February ... 14 ... 1989  
month day year

Approx. - SW. NW. NE. Sec. 12. Twp 16. S, Rg 31. East West

OPERATOR: License # ... 3988  
Name: SLAWSON EXPLORATION COMPANY, INC.  
Address: 104 South Broadway  
City/State/zip: Wichita, Kansas 67202  
Contact Person: Bob Jenkins  
Phone: (316) 263-3201

4240' FSL ... feet from South line of Section  
2260' FEL ... feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039  
Name: L. D. Drilling, Inc.

County: Scott  
Lease Name: YORK "BZ" Well #: 1  
Field Name: Wildcat

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield .X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OAWO ... Disposal .X Wildcat ... Cable  
... Seismic; ... # of Holes

Is this a Prorated Field? ... yes X no  
Target Formation(s): ... Mississippian  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2836' GR (Seis) feet MSL  
Domestic well within 330 feet: ... yes X no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 150'  
Depth to bottom of usable water: 1200'  
Surface Pipe by Alternate: ... 1 X 2  
Length of Surface Pipe Planned to be set: 280'  
Length of Conductor pipe required: None  
Projected Total Depth: 4550'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well X farm pond ... other

If OAWO: old well information as follows:  
Operator: ...  
Well Name: ...  
Comp. Date: ... Old Total Depth ...

DWR Permit #: ...  
Will Cores Be Taken?: ... yes X no  
If yes, proposed zone: ...

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location: ...

Set 280' of 8 3/8 on 2-22-89 200' Act 2 Reg

AFFIDAVIT

PUSHER *Shay Davidson*  
TD *2380* FORMATION  
*1550*  
SURFACE PIPE *8 3/8 @ 310* *115' above SX*  
ANHYDRITE *2265-889* ELEVATION

STARTING TIME & DATE *5:00 PM 3-2-89*  
COMPLETION TIME & DATE *9:30 AM 3-2-89*  
1st PLUG @ *2280* FT. W/ *50* SX  
2nd PLUG @ *1500* FT. W/ *80* SX  
3rd PLUG @ *350* FT. W/ *50* SX  
4th PLUG @ *40* FT. W/ *10* SX  
RAT HOLE CIRCULATED W/ *15* SX  
MOUSE HOLE CIRCULATED W/ *✓* SX  
WATER WELL PLUGGED W/ *✓* SX

CEMENT COMPANY *Allied*  
TECHNICIAN *Richard*

*60-461076*  
*Rec'd 3-11-89*  
*K.C.C.*

5280	1980
4950	1850
4620	1720
4290	1590
3960	1460
3630	1330
3300	1200
2970	1070
2640	940
2310	810
1980	680
1650	550
1320	420
990	290
660	160
330	30

Wichita, Kansas

Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.

15-171-20379-0000

DRILLERS WELL LOG

DATE COMMENCED: 2-22-89  
DATE COMPLETED: 3-02-89

SLAWSON EXPLORATION COMPANY, INC.  
York "BZ" #1  
SW NW NE Sec. 12-16S-31W  
Scott County, Kansas

Elevation: 2838'GR 2843'KB

0 - 310 Surface  
310 - 480 Clay & Sand  
480 - 1117 Soft Shale  
1117 - 2385 Shale  
2385 - 2700 Lime  
2700 - 3130 Shale & Lime  
3130 - 3325 Lime  
3325 - 3490 Shale & lime  
3490 - 3836 Lime  
3836 - 4025 Lime & Shale  
4025 - 4070 Lime  
4070 - 4240 Lime & Shale  
4240 - 4335 Lime  
4335 - 4412 Lime & Shale  
4412 - 4583 Lime  
RTD - 4583

FORMATION DATA	S/T
Anhy	2264 (+579)
B/Anhy	2287 (+556)
Wab	3495 (-652)
Heeb	3875 (-1032)
Tor	3894 (-1051)
Lans	3913 (-1070)
35'	3947 (-1104)
70'	3996 (-1153)
100'	4020 (-1175)
Mun CR	4082 (-1289)
Stk	4177 (-1334)
HP	4215 (-1372)
B/KC	4258 (-1415)
Marm	4289 (-1446)
Paw	4384 (-1541)
Myr St	4418 (-1575)
FS	4438 (-1595)
L/Cher	4460 (-1617)
JZ	4501 (-1658)
Miss	4553 (-1701)
RTD	4583 (-1740)

RECEIVED  
CORPORATION COMMISSION  
MAR 08 1989  
OBSERVATION DIVISION  
Wichita Kansas

SURFACE CASING:

8 5/8" set at 310' W/175 ex.  
60/40 Pozmix, 2% Gel, 3% CC

A F F I D A V I T

STATE OF KANSAS )  
COUNTY OF BARTON) ss

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson  
Greg Davidson

Subscribed and sworn to before me this 7th day of March, 1989.

NOTARY PUBLIC - State of K.  
BESSIE M. DeW. E.F.I.  
My Appt. Exp. 5-20-89

Bessie M. DeW. E.F.I.  
Notary Public: Bessie M. DeW. E.F.I.

My Commission expires: 5-20-89