

STATE OF KANSAS
STATE CORPORATION COMMISSION
2004 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20,376-0000

LEASE NAME York "A"

WELL NUMBER 1-2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 2 TWP. 16 RGE. 31 (X) or (W)

COUNTY SCOTT

LEASE OPERATOR Landmark Oil Exploration, Inc.

ADDRESS 250 N. Water, Suite 308 Wichita, Kansas 67202

PHONE#(316) 265-8181 OPERATORS LICENSE NO. 6113

Date Well Completed 10-2-88

Character of Well D & A

Plugging Commenced 10-2-88 2:00 PM

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-2-88 3:00 P.M.

The plugging proposal was approved on October 2, 1988 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? By operator If not, is well log attached? NO

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	278'	8 5/8"	278	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

50 sx. 60/40 Poz, 6% Gel at 2290', 80 sx. at 1460', 40 sx. at 300', 10 sx. at 40',
15 sx. in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan License No. _____

Address Hays, Kansas

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Landmark Oil Exploration, Inc.


STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, KS. 67530

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 88



Bessie M. DeWerff
Notary Public
Bessie M. DeWerff

5-20-89

DRILLERS WELL LOG

DATE COMMENCED: 9-23-88
DATE COMPLETED: 10-2-88

Landmark Oil Exploration, Inc.
York "A" #1-2
NE SW SE Sec. 2-16S-31W
Scott County, Kansas

Elevation: 2867 GR 2872 KB

0	-	280	Sand & Shale
280	-	1265	Clay
1265	-	1460	Shale & shells
1460	-	1600	Sand
1600	-	2590	Shale
2590	-	4305	Lime & Shale
4305	-	4405	Lime
4405	-	4650	Shale
R.R.D.		4650	

Formation Data

Sample Tops:

B. Anhydrite	2306	(+566)
Heebner	3890	(-1018)
Lansing	3930	(-1058)
Muncie Creek	4095	(-1223)
"H" Zone	4113	(-1241)
Stark	4191	(-1319)
BKC	4275	(-1403)
Marmaton	4304	(-1432)
Pawnee	4398	(-1526)
Myric Station	4434	(-1562)
Fort Scott	4450	(-1578)
Cherokee Sh	4476	(-1604)
Mississippi	4560	(-1688)

SURFACE CASING:

8 5/8" Set @ 278' W/150 sx. 60/40
Pozmix, 2% Gel, 3% CC

RECEIVED
STATE CORPORATION COMMISSION
OCT 11 1988
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON ss

Greg Davidson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 7th day of October 1987.

Bessie M. DeWitt
Notary Public: Bessie M. DeWitt



My commission expires _____

NOTICE OF INTENTION TO DRILL

** CORRECTED **

(see rules on reverse side)

Starting Date October 1 1988

API Number 15- 171-20,376-0000

2

OPERATOR: License # 06113 4656

NE. SW. SE. Sec. 2 Twp. 16. S. Rg. 31. West 990 Ft. from South Line of Section 1650 Ft. from East Line of Section

Name Landmark Oil Exploration & Davis Petroleum

Address 250 N. Water, Suite 308

City/State/Zip Wichita, Kansas 67202

Contact Person Jeff Wood

Phone (316) 265-8181

CONTRACTOR: License # 06039

Name H. P. Drilling

City/State Great Bend, Kansas

Well Drilled For: Oil SWD Infield Mud Rotary

Gas Inj Pool Ext Air Rotary

OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 990 feet County Scott

Lease Name York "A" Well # 1-2

Ground surface elevation 200 feet MSL

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Depth to bottom of fresh water 200

Depth to bottom of usable water 1250

Surface pipe by Alternate: 1 2 X

Surface pipe planned to be set 250

Conductor pipe required N/A

Projected Total Depth 4600 feet

Formation Mississippi

If OWWO: old well info as follows:

Operator

Well Name

Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 9-23-88 Signature of Operator or Agent Title President

For KCC Use:

Conductor Pipe Required 200 feet; Minimum Surface Pipe Required 200 feet per Alt. X 2

This Authorization Expires 3-21-89 Approved By LKM 9-24-88 Date Rec'd 9-21-88

EFFECTIVE DATE: 9-26-88

* WAS: added DAVIS PETROLEUM & H.P. DRILLING

9-22-88 Set 250' - 8 5/8"

Handwritten log with fields: PUSHER Greg Davidson, TD 4650 FORMATION, SURFACE PIPE 8 5/8 @ 278, ANHYDRITE 2289 ELEVATION 2289, STARTING TIME & DATE 11 AM 10-2-88, COMPLETION TIME & DATE 3 PM, 1st PLUG @ 2290 FT. WI 50 SX, 2nd PLUG @ 1460 FT. WI 805X SX, 3rd PLUG @ 900 FT. WI 40 SX, 4th PLUG @ 40 FT. WI 10 SX, RAT HOLE CIRCULATED WI 15 SX, MOUSE HOLE CIRCULATED WI SX, WATER WELL PLUGGED WI SX, CEMENT COMPANY AITKAS, TECHNICIAN A.L., 60/40 por 690, RECEIVED STATE CORPORATION COMMISSION OCT 5 1988, CONSERVATION DIVISION Wichita, Kansas