


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Scott County. Sec. 6 Twp. 16S Rge. 32 ~~XX~~ (W)
Location as "NE/CNW/SW" or footage from lines C NW SE
Lease Owner Yucca Petroleum Co.
Lease Name DeWeese Well No. 1
Office Address P. O. Box 2585, Amarillo, Texas 79105
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed _____ 19____
Application for plugging filed November 20 1969
Application for plugging approved November 20 1969
Plugging commenced November 20 1969
Plugging completed November 20 1969
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4880 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	395'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged well through open end drill pipe w/Halliburton "Light" cement
av. slurry wt. 13.4#/gal.

100 sx - (1050-1500') Across Dakota water sands
25' sx - (335 - 450') bottom of 8-5/8" casing
10 sx - (0 - 40') top of 8-5/8" casing

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF TEXAS, COUNTY OF POTTER, ss.
Eddie C. Podzemny, Jr. (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Eddie C. Podzemny Jr.
P. O. Box 2585, Amarillo, Texas 79105
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of December, 1969

Karen Sue Becker
Notary Public.

My commission expires 6-1-71



Karen Sue Becker, Notary Public in and for Potter County, Texas

DRILLER'S LOG

COMPANY: YUCCA PETROLEUM
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: DEWEESE #1
 LOCATION: C NW SE SECTION 6-16S-32W
 SCOTT COUNTY, KANSAS
 COMMENCED: 11-4-69
 COMPLETED: 11-20-69

0	40	Clay & Sand
40	135	Sand
135	365	Shale & Rock
365	395	Plug & Cement
395	1730	Shale
1730	2344	Shale & Lime
2344	2355	Anhydrite
2355	2390	Shale
2390	2419	Anhydrite
2419	2455	Shale & Red Bed
2455	2705	Shale & Lime
2705	2877	Lime
2877	3295	Lime & Shale
3295	3760	Lime
3760	3845	Lime & Shale
3845	4673	Lime
4673	4723	Mississippi
4723	4790	Mississippi Lime
4790	4880	Lime
	<u>4880</u>	<u>RTD D & A</u>

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 10 1969
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" 20# H-40 R-s Casing set @ 395' cemented with 270 sacks
 Common 3% C.C. 3/4# Flocele per sack.

I, James R. Rodgers, do hereby certify that the above and foregoing
 is a true and correct copy of the log of the DeWeese #1, located
 C NW SE of Section 6, Township 16 South, Range 32 West, Scott County
 Kansas, as reflected by the records of Leben Drilling, Inc.

James R. Rodgers
 James R. Rodgers

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public,
 in and for Barton County, Kansas, this 9th day of December, 1969.

Helen L. Lindenmuth
 Helen L. Lindenmuth

My Commission Expires:
 November 13, 1973