

15-171-20229-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Scott SEC. 25 TWP. 16S RGE. 32 R/W
Location as in quarters or footage from lines:
NW SE SE

			*

Lease Owner Beren Corp.
Lease Name Curry Well No. #2
Office Address 970 Fourth Financial Center, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed March 20, 1982
Application for plugging filed Verbally- March 20, 1982
Plugging commenced 5:00a.m. March 20, 1982
Plugging completed 6:00 a.m. March 20, 1982
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Dry Hole
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
Producing formation N/A Depth to top N/A bottom N/A T.D. 4225
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
			8 jts.	8 5/8" 20#	316'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Plugged to Abandon - Cemented with 140 sacks 50-50 pozmix 4% gel, 3% CaCl2

Set 1st plug @ 1080' with 70 sacks
Set 2nd plug @ 300' with 40 sacks
Set 3rd plug @ 40' with 10 sacks w/solid bridge plug
10 sacks rathole
10 sacks mousehole

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.
C.K. Morrison (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.K. Morrison
555 N. Woodlawn, Bldg. 1 - Suite 207
Wichita, KS (Address) 67208

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1982

Suzanne P. Graef
Notary Public.

My Commission expires: October 26, 1985



RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1982
3-24-82
CONSERVATION DIVISION
Wichita Kansas

March 23, 1982

CONTRACTOR'S WELL LOG

15-171-20229-0000

STATE OF KANSAS RECEIVED
MAR 25 1982
CONSERVATION DIVISION

OPERATOR: Beren Corporation
 CONTRACTOR: KANDRILCO, Inc.
 WELL NAME: Curry #2
 LOCATION: NW SE SE Section 25, T16S-R32W
 Scott County, Kansas
 API NO.: 15-171-20,229
 COMMENCED: March 12, 1982
 COMPLETED: March 20, 1982

Drilled 330' of 12 1/4" hole. Set 316' of new 8 5/8" 20# casing at 316' (KB) with 200 sacks 60-40 pozmix - 3% CaCl₂, 2% Gel. Cement did circulate to surface. Plug was down at 4:30 p.m., March 12, 1982.

FORMATION	TOP'	BOTTOM'
Sand	0	115
Shale	115	330
Sand & Shale	330	1289
Pyrite	1289	1300
Sand & Shale	1300	1720
Sand, Shale & Lime	1720	1960
Sand & Shale	1960	2352
Anhydrite	2352	2373
Shale	2373	2770
Shale & Lime	2770	2860
Shale	2860	3830
Shale & Lime	3830	4065
Lime	4065	4225

STATE OF KANSAS RECEIVED
MAR 25 1982
CONSERVATION DIVISION
Wichita, Kansas

RTD 4225'. Plugged to abandon. Plugged with 140 sacks of 50-50 Pozmix, 4% gel, 3% CaCl. Set 70 sacks at 1080', 40 sacks at 300', 10 sacks at 40' w/solid bridge plug, 10 sacks rathole and 10 sacks mousehole. Plugging was complete at 6:00 a.m., March 20, 1982.

STATE OF KANSAS, COUNTY OF SEDGWICK, SS:

I, George A. Schoepf, Secretary, KANDRILCO, Inc., do hereby state that the above is a true and correct copy of the Driller's Log for the Beren Corporation Curry #2 well located in Scott County, Kansas.

KANDRILCO, Inc.

George A. Schoepf
George A. Schoepf - Secretary

Subscribed and sworn to before me, a Notary Public, in and for the County and State aforesaid, as of this 23rd day of March, 1982.



Suzanne P. Graef
Suzanne P. Graef
Notary Public

My Commission Expires: October 26, 1985