

LEASE NAME Wilkens "A"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 16S RGE. 32W 080 or (W)

COUNTY Scott

Date Well Completed 3/10/97

Plugging Commenced 4:00PM 3/10/97

Plugging Completed 7:30PM 3/10/97

LEASE OPERATOR John O. Farmer, Inc.

ADDRESS P.O. Box 352 Russell, Kansas 67665

PHONE# (913) 483-3144 OPERATORS LICENSE NO. 5135

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/9/97 (date)

by Steve Middleton (XCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation None Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.O. 4750'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	226	8 5/8	226.83	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set

1st Plug @ 2400' w/50sks 5th Plug @ 40' w/10sks Circulated 1st Plug 15 Minutes with 50 Vis Mud  
2nd Plug @ 1350' w/80sks 10sks In Mouse Hole Plugs displaced with mud.  
3rd Plug @ 700' w/40sks 15sks In Rat Hole 245sks 60/40 Poz 6% Gel w/1#FS/sk  
4th Plug @ 250' w/40sks By Allied Cementing Completed @ 7:30 PM 3/10/97

Name of Plugging Contractor Discovery Drilling, Inc. License No. 3F548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

John O. Farmer III (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 97

Margaret A. Schulte  
Notary Public  
Margaret A. Schulte

My Commission Expires: \_\_\_\_\_  
USE ONLY ONE SIDE OF EACH FORM



EFFECTIVE DATE: 2-25-97

State of Kansas

FORM MUST BE SIGNED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 171-20,510 - 0000 ALL BLANKS MUST BE FILLED

SGA? Yes. X No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 2-25-97 month day year

Spot SW-NW-NW Sec .27 Twp .16 S, Rg .32 X West

OPERATOR: License # 5135 JOHN O. FARMER, INC. Address: P.O. BOX 352 City/State/Zip: RUSSELL, KS 67665 Contact Person: Martin K. Dubois Phone: (913) 483-3144

990 feet from South (North) line of Section 330 feet from East (West) line of Section IS SECTION X REGULAR IRREGULAR?

CONTRACTOR: License #: 31548 Name: Discovery Drilling

(NOTE: Locate well on the Section Plat on Reverse Side) County: Scott Lease Name: WILKENS, "A" Well #: 1 Field Name: (wildcat) Is this a Prorated/Spaced Field? yes X no

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... CWMO ... Disposal X Wildcat ... Cable ... Seismic; ... # of Holes ... Other

Target Formation(s): Lansing and Kansas City Nearest lease or unit boundary: 330 Ground Surface Elevation: 2990 feet MSL Water well within one-quarter mile: yes X no

If CWMO: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Public water supply well within one mile: yes X no Depth to bottom of fresh water: 200 Depth to bottom of usable water: 1340 Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 220 Length of Conductor pipe required: NA

Directional, Deviated or Horizontal wellbore? yes X no

Projected Total Depth: 4800 Formation at Total Depth: Mississippi Water Source for Drilling Operations: Existing Irrigation X well farm pond other

If yes, true vertical depth:

Will Cores Be Taken? yes

Bottom Hole Location:

If yes, proposed zone: 220' Alt. II

Exp. 8/20/97

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

RECEIVED KANSAS CO. COMM. 18 202

510

Pusher Tom SPUD DATE 3-4-97 INIT. SM LENGTH SURFACE PLANNED 220 + RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2 @ 227 CONDUCTOR ANHYDRITE T- B-2400 ELEVATION TD 4750 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N SX Arbuckle Plug @ Ft. W/ SX Inq./Council @ Ft. W/ SX Anhydrite Base @ 2400 Ft. W/ 50 SX 1/2 Base Anyh. @ 1350 Ft. W/ 80 SX 1/2, 1/2 Plug @ 700 Ft. W/ 40 SX Bottom Surface @ 250 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SM DATE 3-9-97 TYPE OF CEMENT 60/40 60/40 1/4 Fls Seal STARTING TIME 4:00 (AM/PM) DATE 3-10-97 COMPLETION TIME 6:30 (AM/PM) DATE 3-10-97 CEMENT COMPANY ALL-D