

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 32278
Name: Tengasco, Inc.
Address 1: PO Box 458
Address 2: 1327 Moose Rd.
City: Hays State: KS Zip: 67601 + 9744
Contact Person: Gary Wagner
Phone: (785) 625-6374
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Plattsmouth Depth to Top: 2974 Bottom: 2980 T.D. 3320
LKC Depth to Top: 3106 Bottom: 3288 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-15430 · 00 · 00
Spot Description: _____
NW SE SW Sec. 21 Twp. 17 S. R. 14 East West
990 Feet from North / South Line of Section
3,630 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Keenan B Well #: 4
Date Well Completed: 4-29-1949
The plugging proposal was approved on: 7-8-11 (Date)
by: Ray Dinkel (KCC District Agent's Name)
Plugging Commenced: 7-11-11
Plugging Completed: 7-11-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
	surf.	8.625	864		
	prod.	5.50	3368		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

7/11/11 Perforated 2 holes @ 1520' & 2 holes @ 815'. Ran tbg to 3145'. Mixed & pumped 75 sx cmt w/ 200# hulls, pulled tbg to 2000'. Mixed 100 sx, pulled tbg to 850'. Mixed 110 sx to circ cmt up 5-1/2" & 8-5/8". Pulled tbg & capped csg w/ 10 sx. Capped backside w/ 10 sx. Plugging complete. 305 total sx 60/40 4% gel.

Plugging Contractor License #: 6901 Name: D.S.&W. Well Servicing, Inc.
Address 1: 1822 24th St. Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Phone: (620) 793-5838
Name of Party Responsible for Plugging Fees: Tengasco, Inc.
State of Kansas County, Ellis, ss.
Gary Wagner Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well has been filed, and the same are true and correct, so help me God.

Signature: Gary Wagner

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
AUG 03 2011
KCC WICHITA DR