

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

15.051.01401.00.00

OPERATOR: License #: 5145
Name: Dreiling Oil, Inc.
Address 1: P.O. Box 550
Address 2: _____
City: Hays State: Ks Zip: 67601 + _____
Contact Person: Terry W. Piesker
Phone: (785) 625-8327
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Conglomerate Depth to Top: 3340' Bottom: 3377' T.D. 339.5'
L-KC Depth to Top: 3079' Bottom: 3264' T.D. _____
Topeka Depth to Top: 2781' Bottom: 2945' T.D. _____

API No. 15 - 5-24-59
Spot Description: _____
NW NE NE Sec. 10 Twp. 12 S. R. 16 East West
330 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: Dickinson "A" Well #: 3
Date Well Completed: 5-24-59
The plugging proposal was approved on: 7-13-11 (Date)
by: Bruce Basye (KCC District Agent's Name)
Plugging Commenced: 8-1-11
Plugging Completed: 8-1-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Conglomerate	oil and water	Surface	8 5/8"	216'	none
L-KC	" "	Long String	5 1/2"	3412'	none
Topeka	" "				

RECEIVED
AUG 1 8 2011
8-8-11
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 7/8" Tubing Open Ended to 2760'. Mixed 115 sxs. 60/40 Poz with 4% Gel and 250# hulls. Pulled up to 1644' and mixed 145 sxs. 60/40 Poz with 4% Gel and 250# Hulls. Pulled Tubing and tied to 5 1/2" Casing. Mixed 35 sxs. 60/40 Poz 4% Gel and pressured to 500#. SIP- 400#. Tied to 8 5/8" Casing and mixed 5 sxs. 60/40 Poz and pressured to 250# and SIP- 250#. Job complete.

Plugging Contractor License #: 99996 Name: Allied Cementing Company, LLC.
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + .0031
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: Dreiling Oil, Inc.

State of Kansas County, Ellis, ss.
Terry W. Piesker Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Terry W. Piesker

de