

KANSAS

FORM CP-3  
Rev. 1-8-82

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT REPORT

API Number 15-053-20, 767<sup>5</sup>200 Colorado Derby Building  
Wichita, KS 67202Operator's Full Name Rains & Williamson Oil Company, Inc.Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202Lease Name Nicnke Well No. 1Location NW NW SE Sec. 34 Twp. 14 Rge. 9 (East) (West)County Ellsworth Total Depth 3230'Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒Other well as hereinafter indicated ☐Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour: 8:15 PM Day: 16 Month: May Year: 1982Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

The above well was plugged as follows:

Hole circulated and Filled with mud. 50 sacks cement pumped through drill pipe at 600'. 30 sacks cement pumped through drill pipe at 200'. Plug and 1/2 sack bulls pushed to 40' and hole cemented to base of collar with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50/50 Pozmix w/2% gel and 3% C.C.Amount of Surface Casing: 8 3/4" - 208 - 140 sacks 50/50 Pozmix 2% gel 3% C.C.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
05-24-82  
MAY 24 1982

CONSERVATION DIVISION  
Wichita, Kansas

6-3-82  
368-W