

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-053=20715-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name C. L. Morris Oil Corporation

Complete Address 100 So. Main, 200 Heritage Center, Wichita, Kansas 67202

Lease Name Vopot Well No. #1

Location Center of SW-NW Sec. 31 Twp. 14S Rge. 9 (East) (West)

County Ellsworth Total Depth 3085

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Ramco Drilling Corporation

Address 100 So. Main St., 200 Heritage Center, Wichita, Kansas 67202 License No. _____

Operation Completed: Hour: 9:00PM Day: 12 Month: Sept. Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

8 5/8"-307' sp. cuc. with 225 sacks common-2% Gel.-3% Cal. Cl.

Ordered 125 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem-with heavy mud between all plugs.

1st plug @ 690' with 70 sacks cement

2nd plug @ 300' with 40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' with 10 sacks cement.

5 sacks of cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1981

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas

Signed: Gilbert R. Schuk
Conservation Division Agent

INVOICED

DATE 10/30/81
BY 8 to N