

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-053-20, 766-00-00

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Rains & Williamson Oil Company, Inc.

Complete Address 435 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name Haase Well No. 1

Location SW SW SW Sec. 27 Twp. 14 Rge. 9 (~~East~~) (West)

County Ellsworth Total Depth 3260'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Co. Tools and Allied Cementing Co., Inc.

Address \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour: 4:15 PM Day: 25 Month: May Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows: Elevation 1629 KB

Hole circulated and filled with mud. 50 sacks cement pumped through drill pipe at 500'. 30 sacks cement pumped through drill pipe at 220'. Hole filled with mud to 40'. Plug and 1/2 sack bulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement through pipe.

Cement used: 50/50 Pozmix w/2% gel and 3% cc

Amount of Surface Casing: 8 1/8" - 225 - 150 sacks 54/50 2% - 3%

I hereby certify that the above plugging instructions were given as herein stated.

Signed: \_\_\_\_\_  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

3 1/2" of rain - couldn't get close to rig.

Signed: [Signature]  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
JUN - 4 1982  
06-04-82  
CONSERVATION DIVISION  
Wichita Kansas

DATE 6-3-82  
INSTR. NO. 400-11