



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Beren Corporation

Complete Address 970 Fourth Financial Center, Wichita, Kansas

Lease Name McDaniel Well No. 1

Location C NE NW Sec. 36 Twp. 15 Rge. (E) (W) 34

County Logan Total Depth 4670'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12 Day 12 Month 8 Year 1975

The above well was plugged as follows:

RTD 4670' 8 5/8 csg set 340' cwc 200 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 1300' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/20/75

INV. NO. 1790-W

Signed: Leo Massey
Well Plugging Supervisor