

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-199-20,095-00-00 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Arrowhead Petroleum, Inc. OPERATORS LICENSE NO. 5533

ADDRESS P. O. Box 8287, Wichita, KS 67220 PHONE # (316) 681-3921

LEASE (FARM) Robben WELL NO. 1-8A WELL LOCATION NW SE4 COUNTY Wallace

SEC. 8 TWP. 14 RGE. 40 (~~EXX~~ (W) TOTAL DEPTH 5200 PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 13-3/8 SET AT 501 CEMENTED WITH 300 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug at 2750'-25 sacks; 2nd plug at 1700'-100 sacks,

& one sack hulls; 3rd plug at 550'-40 sacks; 4th plug at 40', solid bridge to surface 25 sacks; 15 sacks in rathole,

10 sacks in mousehole: 60/40 posmix, 6% gel, 3% ca.cl.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACO-1 FILED? no

(If not, explain)

Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11-12-86 2:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wally W. Towns PHONE # (913) 462-2123

ADDRESS R. R. #2, Box 657, Colby, KS 67701

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton

(Operator or Agent)  
Jack K. Wharton, Sec./Treas.

DATE: 11-14-86