

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-199-20,094-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Arrowhead Petroleum, Inc. OPERATORS LICENSE NO. 5533

ADDRESS P. O. Box 8287 Wichita, KS 67220 PHONE # (316) 681-3921

LEASE (FARM) Robben WELL NO. 1-8 WELL LOCATION Approx NW SE/4 COUNTY Wallace

SEC. 8 TWP. 14S RGE. 40 (E) or (W) (W) TOTAL DEPTH 1788' PLUG BACK TO

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 370' CEMENTED WITH 235 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug 100 sacks and 2 sacks celoflake at 1340';
2nd plug 100 sacks and 1 sack celoflake at 440'; 3rd plug 10 sacks at 40'. Solid bridge to surface, 15 sacks in
rathole, 10 sacks mousehole; all cement 60/40 posmix, 6% gel, 3% ca. cl.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? no IS ACC-1 FILED? no
(If not, explain) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10-31-86 10:30 p.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Wally W. Towns PHONE # (913) 462-2123

ADDRESS R. R. #2, Box 657 Colby, KS 67701 11-06-86

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422 NOV 6

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack L. Partridge

(Operator or Agent)
Jack L. Partridge, Vice President

DATE: 11-5-86