

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Wallace County, Sec. 9 Twp. 14S Rge. (E) 42 (W)

Location as "NE/CNW&SW" or footage from lines C NW/4 SE/4

Lease Owner Cooperative Refinery Association

Lease Name Goodrich "B" Well No. 1

Office Address Box 765 Gt. Bend, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed May 31 19 60

Application for plugging filed June 2 19 60

Application for plugging approved Verbal permission obtained 19

Plugging commenced May 31 19 60

Plugging completed May 31 19 60

Reason for abandonment of well or producing formation

Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 5427 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE   | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 441    | -0-        |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 450', dumped 1 sack hulls, dumped in 25 sacks cement thru drill pipe. Hole plugged.

STATE CORPORATION COMMISSION

JUN 6 1960

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Honaker Davis Drlg. Co. (If additional description is necessary, use BACK of this sheet)

Address Gt. Bend, Ks.

STATE OF Kansas COUNTY OF Barton ss.  
Marvin D. Sullivan (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. D. Sullivan  
Box 765, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 2 day of June, 19 60

My commission expires November 8, 1960

Betty S. Edman  
Notary Public.

15-199-00006-00-00

DRILLERS LOG

Goodrich B #1

Elevation: 3856' D.F.

Loc: C NW/4 SE/4

Casing: 8 5/8" @ 441' w/ 200 sx.

Sec: 9-14S-42W

Comm: 5-4-60 Comp: 5-31-60

Wallace County, Kansas

Operator: Cooperative Refinery Ass'n.

R.T.D. 5427'

Contractor: Honaker Davis Drlg. Co.

| <u>From</u> | <u>To</u> | <u>Formation</u>        |
|-------------|-----------|-------------------------|
| 0           | 470       | Clay and sand           |
| 470         | 990       | Shale and sand streaks  |
| 990         | 1552      | Shale                   |
| 1552        | 1660      | Shale with iron streaks |
| 1660        | 1755      | Shale with sand streaks |
| 1755        | 1945      | Shale and iron          |
| 1945        | 2200      | Shale and shells        |
| 2200        | 2350      | Shale and redbed        |
| 2350        | 2715      | Redbed                  |
| 2715        | 2854      | Redbed and shale        |
| 2854        | 2888      | Anhydrite               |
| 2888        | 3205      | Shale and redbed        |
| 3205        | 3420      | Redbed and lime         |
| 3420        | 3490      | Shale with lime streaks |
| 3490        | 3544      | Shale and redbed        |
| 3544        | 3675      | Lime                    |
| 3675        | 4268      | Lime and shale          |
| 4268        | 4695      | Lime                    |
| 4695        | 4746      | Chert and lime          |
| 4746        | 4774      | Shale and lime          |
| 4774        | 4818      | Lime                    |
| 4818        | 5172      | Lime and shale          |
| 5172        | 5397      | Lime                    |
| 5397        | 5427      | Lime and chert          |
| 5427        |           | R.T.D.                  |

CONSERVATION COMMISSION  
 JUN 6 1960  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 06-06-1960

(STATE OF KANSAS )

(COUNTY OF BARTON)

I hereby certify that the above is a true and correct copy of the log on the Goodrich "B" #1 well, located C NW/4 SE/4 of Section 9-14S-42W, Wallace County, Kansas.

M.D. Sullivan

Subscribed and sworn to before me this 2 day of June 1960.

Betty S. Edman

My commission expires: November 8, 1960.