

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.--82-3-117

API NUMBER 15-199-20,141-00-00

LEASE NAME Purvis Farms

WELL NUMBER 1-24X

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

1100' Ft. from S Section Line

460' Ft. from E Section Line

SEC. 24 TWP. 14 RGE. 43X (E) or (W)

COUNTY Wallace

Date Well Completed 3-4-88

Plugging Commenced 3-3-88

Plugging Completed 3-4-88

LEASE OPERATOR TXO Production Corporation

ADDRESS 155 N. Market, Suite 1000

PHONE# (316) 269-7655 OPERATORS LICENSE NO. 5171

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. 6 Hays, Ks. State plugger Ed Schumacher

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	320'	None
				8 5/8"	766'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

1st plug from 2830' to 2750' w/20sx pump mud to 2240'; 2nd plug 2240' to 2040' w/50sx pump mud to 1990'; 3rd plug from 1990' to 1590' w/100sx pump mud to 815'; 4th plug from 815' to 695' w/30sx pump mud to 40'; 5th plug 40' to surface w/10sx. Rathole 15sx; mouse  
 (If additional description is necessary, use BACK of this form.) (cont. on back)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 801 Union Center Wichita, Ks. 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 801 Union Center Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 9th day of March



Janet A. Stuck  
 NOTARY PUBLIC  
 CONSERVATION DIVISION  
 Wichita, Kansas

My Commission Expires: 12-29-90

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 10 1988

03-10-88

hole 15sx; 60-40 posmix, 6% gel, 3sx flocel.

(11/10/01)  
7/1