

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-199-20221-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Red Oak Energy, Inc. KCC LICENSE # 3581
(owner/company name) (operator's)
ADDRESS 200 W. Douglas #510 CITY Wichita
STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-9925
LEASE NE Mt. Sunflower WELL# 1-30 SEC. 30 T. 15 R. 41 (East/West)
- NE - NE - NE SPOT LOCATION/QQQQ COUNTY Wallace

4950 FEET (in exact footage) FROM (S)N (circle one) LINE OF SECTION (NOT Lease Line)
330 FEET (in exact footage) FROM (E)W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS
SURFACE CASING SIZE 8 5/8" SET AT 369 CEMENTED WITH 60/40 Pos 250 SACKS
PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 3809 T.D. 5250 PBDT _____ ANHYDRITE DEPTH 2750-2778'
(G.D./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud, set 1st plug @ 2780' w/25 sx; 2nd plug @ 1760' w/100 sx; 3rd plug @ 400' w/40 sx; 4th plug @ 40' w/10 sx; 15 sx in rathole; 10 sx in mousehole, 60/40 posmix, 6% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jim Renner PHONE# (719) 767-5888
ADDRESS _____ City/State Cheyenne Wells, Colorado

PLUGGING CONTRACTOR Murfin Drilling Company KCC LICENSE # 30606
(company name) (contractor's)
ADDRESS 250 N. Water PHONE # (316) 167-3241

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) NOV 2 1994 11-22.94

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 11/17/94 AUTHORIZED OPERATOR/AGENT: Jim C. Renner
(signature)