

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-171-20,264-0000

LEASE NAME CRIST "C"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

3300 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 25 TWP. 20S RGE. 34 (X) of (W)

COUNTY Scott

Date Well Completed 1-20-84

Plugging Commenced 5-31-85

Plugging Completed 6-3-85

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 4714 Bottom 4718 T.D. 5000'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow (4714-18')	Oil & Water	1175	0	8-5/8"	26 jts	0
		4915	0	4-1/2"	141 jts	45 joints (1730')

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spotted 50 sacks cement from 4718' to 4300'. Cut off 4-1/2" casing at 1730', pulled casing to 1045', spotted 50 sacks cement from 1225' to 1045'. Pulled casing to 360', spotted 25 sacks from 450' to 360'. Spotted 10 sacks cement from 40' to 3', cut off casing and cap well.

Pulled a total of 45 joints of 4-1/2" 10.5# casing (1730')
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547


Address 620 South Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

Paul Campbell (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Paul Campbell

(Address) P. O. Box 351, Liberal, Kansas 67901



Subscribed and sworn to before me this 23rd day of August, 19 85
Beverly J. Williams
 STATE CORPORATION COMMISSION
 My Commission Expires: November 21, 1986

DRILLERS LOG

OPERATOR: Anadarko Production Company
 Box 351
 Liberal, Kansas 67901

CONTRACTOR: Slawson DRILLING Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

WELL NAME: Crist 'C' #1
 W/2 SW NW Sec.25-20S-34W
 Scott County, Kansas

COMMENCED: 11/16/83

COMPLETED: 5 p.m. 11/30/83

SURF. CASING: 8-5/8" set at 1175' with 550 sx cement

PROD. CASING: 4-1/2" set at 4917' with 275 sx cement

0' to 1178' Sand & Shale
 1178' to 3200' Shale
 3200' to 3852' Shale & Lime
 3852' to 4035' Lime & Shale
 4035' to 4338' Shale & Lime
 4338' to 5000' Lime
 RTD 5000'

I hereby state the above is an accurate copy of the drillers log on the
 Crist 'C' #1 for Anadarko Production Company.

James C. Remsberg
 James C. Remsberg, President
 Slawson Drilling Company, Inc.

RECEIVED
 STATE CORPORATION COMMISSION

JAN 24 1985

CONSERVATION DIVISION
 Wichita, Kansas

Subscribed and sworn to me this
 3rd day of February, 1984

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1985

RECEIVED
 FEB 03 1984
 P. J. DUNN, JR., NOTARY
 WICHITA, KANSAS

