


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plat

Scott County, Sec. 15 Twp. 20S Rge. 34W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NW NW

Lease Owner Imperial oil company
Lease Name Minnix Well No. 1
Office Address 720 - 4th Financial Center, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed 10-27 1976
Application for plugging filed 10-27 1976
Application for plugging approved 10-27 1976
Plugging commenced 10-27 1976
Plugging completed 10-27 1976

Reason for abandonment of well or producing formation
No commercial quantities of oil or gas encountered.

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 5015
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Shale	Surf	405	8-5/8"	397'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Fluid to 1300', plug, 70 sx cement;
Fluid to 300', plug, 20 sx cement;
Fluid to 40', plug, 1/2 sx hulls, 10 sx cement.

11-12-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
701 First National Building
Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF ss.
JAMES L. DONELSON (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) James L. Donelson
701 First Nat'l Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of November, 19 76

Ella Priess
Notary Public.

My commission expires 8-25-80



DRILLERS' LOG

IMPERIAL OIL COMPANY
 No. 1 Minnix
 C NW NW, Sec. 15-20S-34W
 Scott County, Kansas

Commenced: 10-16-76
 Completed: 10-27-76

Surface Casing: 397' of
 8-5/8" cemented w/175 sx
 light cement, 125 sx common
 cement, 30 cc. 10-17-76

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 405
Shale	405 - 980
Shale & Sand	980 - 2060
Shale w/ lime streaks	2060 - 2640
Shale & Lime	2640 - 2950
Lime & Shale	2950 - 3300
Shale & Lime	3300 - 3444
Lime & Shale	3444 - 3657
Shale & Lime	3657 - 4010
Lime	4010 - 4310
Shale streaks & Lime	4310 - 4415
Lime & Shale Streaks	4415 - 4529
Lime	4529 - 4615
Lime & Shale	4615 - 4648
Lime	4648 - 4820
Lime, Shale & Sand	4820 - 4865
Lime	4865 - 5015 BFD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
 JAMES L. DONELSON

STATE OF KANSAS:

Subscribed and sworn to before me this 10th day of November 1976.

Elia Priess
 Elia Priess, Notary Public

