

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Scott County. Sec. 17 Twp. 20S Rge. (E) 34 (W)

Location as "NE/CNWSW" or footage from lines C SW NE  
Lease Owner Morrison Producing Company  
Lease Name Boyer Well No. 1  
Office Address 400 North Main, El Dorado, Kansas 67042  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 5-19 19 69  
Application for plugging filed 5-19 19 69  
Application for plugging approved 5-19 19 69  
Plugging commenced 5-19 19 69  
Plugging completed 5-19 19 69  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5017 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	451'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 100 sacks 50/50 Posmix @ 850'  
Spotted 20 sacks 50/50 posmix @ 370'  
Bridged @ 40' 1/2 sack hulls  
Plugged 10 sacks

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.  
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1969

(Address)

Ulanda Nichols  
Notary Public.

My commission expires April 1, 1971

DRILLER'S LOG

COMPANY	Morrison Producing Company
CONTRACTOR	LEBEN DRILLING, INC.
FARM	BOYER #1
LOCATION	C SW NE SECTION 17-20S-34W
	SCOTT COUNTY, KANSAS
COMMENCED	5-3-69
COMPLETED	5-19-69

---

0	190	Sand, Clay
190	220	Blue Shale
220	456	Sand, Shale
456	785	Shale
785	1125	Blue Shale
1125	1480	Red Bed Shale
1480	1500	Shale w/ Lime Streaks
1500	1800	Shale, Sand Streaks
1800	2075	Shale, Lime Streaks
2075	2270	Shale, Lime
2270	2285	Anhydrite
2285	2558	Shale, Lime
2558	2695	Lime, Shale
2695	2814	Lime
2814	2964	Washing Over
2964	3100	Shale, Lime
3100	3315	Lime, Shale
3315	3435	Shale, w/ Lime Streaks
3435	3575	Lime, Shale
3575	5017	Lime
	<u>5017</u>	<u>RTD - D. &amp; A.</u>

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas

---

8 5/8" 20# new surface casing set @ 451' cemented with 200 sacks Posmix and 125 sacks Common cement 3% cc

---

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Boyer #1 Well, located C SW NE of Section 17, Township 20 South, Range 34 West, Scott County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 22nd day of May, 1969.

Ulanda Nichols  
Ulanda Nichols

My Commission Expires:  
April 1, 1971