

15171-20261-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Scott SEC. 23 TWP. 20S RGE. 34
 Location as in quarters or footage from lines:
C NW NW SE/4

Lease Owner Anadarko Production Company
 Lease Name Crist "E" Well No. 1
 Office Address Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed 11/5/83
 Application for plugging filed 11/21/83
 Plugging commenced 11/4/83
 Plugging completed 11/5/83
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
 Producing formation _____ Depth to top _____ bottom T.D. 4950
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	1176'	0'	1176'	8-5/8	1176	0'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. All cement plugs are 60-40 Pozmix + 2% Gel + 3% CaCl.
Spot 50 sxs 2190' to 1940', spot 50 sxs 1600' to 1350', 40 sxs 1230' to 1080', push wiper
plug to 40', spot 10 sxs cement 40' to 0', circulate 15 sxs cement in rathole, circulate
all thru plug job.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company
200 Douglas Building, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Seward, ss
Paul Campbell (employee of owner) or (~~owner~~) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 83

Elizabeth J. Hooper
 Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION
 My Commission expires
DEC 20 1983
12-20-83
 CONSERVATION DIVISION
 Wichita, Kansas

ELIZABETH J. HOOPER
 Seward County, Kansas
 My Appt. Expires 7-26-87