

15-171-20240-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Scott SEC. 24 TWP. 20S RGE. 34 E/W
 Location as in quarters or footage from lines:
NE NE SW

Lease Owner Anadarko Production Company
 Lease Name Crist "A" Well No. 1
 Office Address Box 351, Liberal, Kansas 67901
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
 Date Well Completed 11/23/82
 Application for plugging filed 12/7/82
 Plugging commenced 11/23/82
 Plugging completed 11/23/82
 Reason for abandonment of well or producing formation _____

Locate Well
 correctly on above
 Section Platt.

Dry hole
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4952
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	533	0	533	8-5/8	533	0

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set. Spotted 50 sxs cmt 1200' to 1100', spotted 50 sxs cmt
900' to 800', spotted 35 sxs cmt 850' to 750', 10 sxs cmt 40' to 0', 10 sxs cmt in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.
830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Seward, ss.
Paul Campbell (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
Box 351, Liberal, Kansas 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 82

My Commission expires: _____
 Elizabeth J. Hooper
 Notary Public.

DEC 14 1982
 12-14-82
 CONSERVATION DIVISION
 Wichita, Kansas

GABBERT-JONES, INC.
WICHITA, KAS. 67202

DRILLERS WELL LOG

CRIST "A" #1
C NE NE SW Sec. 24-20S-34W
Scott County, Kas.

Commenced: 11/8/82
Completed: 11/25/82

OPERATOR: ANADARKO PRODUCTION COMPANY
LIBERAL, KAS. 67901

Depth From	To	Formation	Remarks
0	540	Sand-Shale	Ran 13 jts. of 20# 8 5/8" csg. set @ 533' cemented w/400 sx. common - 3% CC - PD @ 2:30 AM 11/9/82
540	1180	Shale-Sand	
1180	3087	Shale-Lime	
3087	3199	Lime-Shale	
3199	3446	Shale-Lime	
3446	3578	Lime-Shale	
3578	3880	Shale-Lime	
3880	4010	Lime-Shale	
4010	4060	Shale-Lime	
4060	4088	Lime-Shale	
4088	4285	Shale-Lime	
4285	4387	Lime-Shale	
4387	4554	Shale-Lime	
4554	4627	Lime-Shale	
4627	4755	Shale-Lime	
4755	4801	Lime-Shale	
4801	4935	Shale-Lime	
4935	4952	Lime-Shale	
4952 - TD			D & A.

State of Kansas]
County of Sedgwick]

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton, II
James S. Sutton, II - Pres.

Subscribed & sworn to before me.
this 23rd day of November, 1982.

Lola Lenore Costa
Lola Lenore Costa - Notary Public.
My Commission expires Nov. 21, 1984.

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1982

CONSERVATION DIVISION
Wichita, Kansas