

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-171-20,239-0000

LEASE NAME Crist "B"

WELL NUMBER 1

SPOT LOCATION C NW NE NW

SEC. 24 TWP. 20S RGE. 34 KK) or (W)

COUNTY Scott

Date Well Completed 3/25/83

Plugging Commenced 11/13/84

Plugging Completed 11/14/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Anadarko Production Company

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #1, Dodge City

Is ACO-1 filed? yes If not, is well log attached? no

Producing formation Lansing Depth to top 4233' bottom 4235' T.D. 4236'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS \_\_\_\_\_ CASING RECORD \_\_\_\_\_

STATE CORPORATION COMMISSION  
RECEIVED  
DEC 27 1984  
12-27-84  
CONSERVATION DIVISION  
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
St. Louis	water & oil	4848	4852	8-5/8"	536'	3'
Morrow	oil & water	4789	4813	4-1/2"	4877'	3'
Lansing	water	4233	4235			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. 11/13/84 Pumped 1 sack hulls, 25 sacks cement, from 4236' to 3936', 10 sacks gell, 25 sacks cement from 2436' to 2136', 5 sacks of gell 90 sacks cement from 1386 to surface, cement fell 30 feet.  
11/14/84 Pumped 10 sacks cement to surface. Cut off 8-5/8" and 4-1/2" casing 3' below ground level and capped.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547  
Address 620 S. Lincoln, Liberal, Kansas

STATE OF KANSAS COUNTY OF SEWARD, ss.

Paul Campbell (employee of operator) or  
~~XXXXXXX~~ of above-described well, being first duly sworn on oath, says: That  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God.

(Signature) Paul Campbell

(Address) P. O. Box 351, Liberal, KS 67901

BEVERLY J. WILLIAMS  
Seward County, Kansas  
My Appl. Exp. 11/21/86  
My Commission expires: November 21, 1986

SUBSCRIBED AND SWORN TO before me this 20th day of Dec., 1984

Beverly J. Williams  
Notary Public

GABBERT-JONES, INC.  
WICHITA, KAS. 67202

DRILLERS WELL LOG

15-171-20239-0000

CRIST "B" #1  
C NW NE NW Sec. 24-20S-34W  
Scott County, Kas.

Commenced: 10/23/82  
Completed: 11/8/82


OPERATOR: ANADARKO PRODUCTION CO.  
LIBERAL, KAS. 67901

Depth From- To	Formation	Remarks
0 535	535 1164 Sand-Shale Shale	Ran 13 jts. of 20# 8 5/8" csg. set @ 526' cemented w/350 sx. cement - 3% CC - PD @ 7:00 PM 10/23/82
1164 1840 1840 1961 1961 2164 2164 3168 3168 3280 3280	1840 1961 2164 3168 3280 Sand-Shale Redbed Redbed Shale Shale-Lime Lime-Shale Shale-Lime	Ran 114 jts. of 10 1/2# csg. set @ 4877' cemented w/100 sx. Lite .75% Tic - 275 sx. Salt Sat. Posmix w/.5% Tic PD @ 12:30 AM 11/8/82
3591 3734 3734 4020 4020 4137 4137 4324 4324 4375 4375 4467 4467 4523 4523 4622 4622 4665 4665 4761 4761 4809 4809	3734 4020 4137 4324 4375 4467 4523 4622 4665 4761 4809 Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime Lime-Shale Shale-Lime	
4879 - TD.		

STATE OF KANSAS ]  
COUNTY OF SEDWICK ]

I, the undersigned, being duly sworn on oath, state that the above Drillers Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

  
James S. Sutton, II - Pres.

Subscribed and sworn to before me  
this 22nd day of November, 1982.

  
Lola Lenore Costa, Notary Public  
My Commission expires November 21, 1984.



RECEIVED  
STATE OF KANSAS COMMISSION

NOV 09 1982

CONSERVATION DIVISION