


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

Scott County. Sec. 5 Twp. 20 Rge. 32 ~~EW~~  
Location as "NE/CNW1SW1" or footage from lines \_\_\_\_\_  
\_\_\_\_\_ G SW 1/4

Lease Owner Dorchester Exploration inc  
Lease Name Murphy Well No. 1  
Office Address Midland, Texas  
Character of Well (Completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Dry Hole

Date Well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed 3-30 1976  
Application for plugging approved 4-1 1976  
Plugging commenced 4-2 1976  
Plugging completed 4-2 1976

Reason for abandonment of well or producing formation \_\_\_\_\_  
Not of Commercial Value  
If a producing well is abandoned, date of last production \_\_\_\_\_  
\_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Balthazor  
Producing formation Hugoton Depth to top 2735 Bottom 2764 Total Depth of Well 2900'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	POT IN	PULLED OUT
				8 5/8"	350'	0
				4 1/2"	2900'	210'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to  
\_\_\_\_\_ feet for each plug set.

Pumped 2 sacks hulls & 10 sacks cement to 2600'- Displaced w/ 4 sacks gel  
Pumped 20 sacks cement 1200' to 980'- Displaced w/ 3 sacks gel  
Pumped 10 sacks cement 350' to 230'- Displaced w/ 2 sacks gel.  
Pulled 210' of 4 1/2" casing- Put bridge & 10 sacks cement 40' to 0'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling  
Box F, Sublette, Kansas

STATE OF COLORADO COUNTY OF DENVER ss.  
JAMES JAMESON (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Jameson

1400 Metrobank Bldg., Denver, Co. 80202  
(Address)

Subscribed and Sworn to before me this 12th day of April 1976

My commission expires December 18, 1978

Gerardine Jancia  
Notary Public.

4-14-76