

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior Inc
Address 1: P.O. Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846 + _____
Contact Person: Kevin Wiles, Sr
Phone: (620) 275-2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 009-24, 808 · 00 · 01
Spot Description: SW 25-20S-13W
SW SW SW _____ Sec. 25 Twp. 20 S. R. 13 East West
~~400~~ 420 Feet from North / South Line of Section
~~330~~ 5141 Feet from East / West Line of Section
GPS-KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Barton
Lease Name: Marmie Well #: 2-25
Date Well Completed: 1/14/05
The plugging proposal was approved on: 11/15/2010 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: 8/26/11
Plugging Completed: 8/29/11

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|--------|---------------|------------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| | | Surface | 8 5/8" | 315 | 300 Sacks Cement |
| | | Production | 4 1/2" | 3609 | 150 Sacks Cement |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand at 3197', bailed 4 sacks cement on sand. Ripped casing at 2400' & 2020', 1920' & 1680. Pulled casing up to 1550' & pumped 125 sacks cement & 300# hulls. Pulled to 700' & pumped 40 sacks cement & 100# hulls. Pulled to 315' & pumped 40 sacks cement & 100# hulls. Pulled to 150' & circulated with 50 sacks cement to surface.

Plugging Contractor License #: 31925 Name: Quality Well Service, Inc
Address 1: 190 US Hwy 56 Address 2: _____
City: Ellinwood State: KS Zip: 67526 + _____
Phone: (620) 727-3409

RECEIVED
SEP 09 2011
KCC WICHITA

Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of KANSAS County, Finney, ss.
Kevin Wiles SR Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____

de