

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 3273
Name: HERMAN L. LOEB, LLC
Address 1: P.O. Box 838
Address 2: _____
City: Lawrenceville State: IL Zip: 62439 + 0838
Contact Person: Shane Pelton
Phone: (719) 340-8987
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 3,524' Bottom: 3,536' T.D. 3,999'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-097-21090-00-00
Spot Description: _____
SE NW Sec. 14 Twp. 29 S. R. 18 East West
3,300-3362 Feet from North / South Line of Section
3,300 3290 Feet from East / West Line of Section
GPS - KCC
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Kiowa
Lease Name: UNRUH Well #: 4-B
Date Well Completed: _____
The plugging proposal was approved on: 8-18-2011 (Date)
by: Steve Durrant (KCC District Agent's Name)
Plugging Commenced: 9-1-2011
Plugging Completed: 9-1-2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Log Tech of KS -tag	@3999' &	show perfs @	3524 to 3536

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Log Tech set CIBP @ 3500' w/2 sx cmt. Load & pressure test csg to 300 lbs (good) Perferate @ 1175'. Pump 225 sx cmt down 4.5 csg. max press. 1300 lbs no circulation. Shut in press. 200 lbs. Hook up to surface csg & pump 125 sx cmt @ 200 lbs shut in. Used 60/40 posmix w/4 % gel.

Plugging Contractor License #: 99996 Name: Allied Cementing Co. LLC
Address 1: P.O. Box 31 Address 2: _____
City: Russell State: Kansas Zip: 67665 + 0031
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: HERMAN L. LOEB LLC
State of ILLINOIS County, _____, ss.
Harold Tracy Hollis Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Harold Tracy Hollis

RECEIVED

SEP 12 2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA