

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Lonestar Oil co.
Address: PO Box 417 Victoria, Ks. 67671
Phone: (785) 735 2725 Operator License #: 31428
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 7-29-11 (Date)
by: Case Morris (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Kansas City Depth to Top: 3050 Bottom: 3234 T.D. 3250

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-167-19151-00-01
Lease Name: Foster B
Well Number: 18
Spot Location (OOOO): C - N $\frac{1}{2}$ - NW - NW
330 Feet from North South Section Line
660 Feet from East West Section Line
Sec. 3 Twp. 14 S. R. 15 East West
County: Russell
Date Well Completed: 1-19-40
Plugging Commenced: _____
Plugging Completed: 7-29-11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	922	10"	922	0
		0	3065	7"	3065	0
		3042	3298	4"	256	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran Tubing to 2925 and pumped 10 sx gel, 50sx cement, 100 pounds hulls. Pulled to 1725 pumped 8 gel, 100 cement 200 hulls.
Pulled to 925 pumped 75 cement, 200 hulls. Pulled to 400' pumped 80 sx and circulated cement. Pulled tubing and topped off well.

Name of Plugging Contractor: Express Well Service License #: 6426
Address: Box 19 Victoria, Ks. 67671

Name of Party Responsible for Plugging Fees: Lonestar Oil

State of Kansas County, Ellis, ss.

Jeff Crawford (Employee of Operator) or (Operator) on above-described well, being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

STATE OF KANSAS
NOTARY PUBLIC
DARLENE BRAUN
My Appl Exp 6-2-13

(Signature) [Signature]
(Address) _____

SUBSCRIBED and SWORN TO before me this 26th day of August, 2011

Darlene Braun My Commission Expires: 6-2-13 **RECEIVED**
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 12 2011
KCC WICHITA

AK