

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-171-20,564-0000

LEASE NAME #1 France "A"

RECEIVED
8-31-01
AUG 31 2001

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1125' Ft. from (S) Section Line

1900' Ft. from (E) Section Line

KCC WICHITA

LEASE OPERATOR Pickrell Drilling Company, Inc.

SEC. 15 TWP. 18 SRGE. 32 (E) or (W)

ADDRESS 100 S. Main, Suite 505 - Wichita, KS. 67202-3738

COUNTY Scott

PHONE (316) 262-8427 OPERATORS LICENSE NO. 5123

Date Well Completed 8-17-01

Character of Well D&A

Plugging Commenced 8-17-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-17-01

The plugging proposal was approved on 8-14-01 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? Yes

Producing Formation None Depth to Top _____ Bottom _____ T.D. 4685

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface Casing			8 5/8"	271' KB	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section. P&A as follows: 50sx @ 2330', 50sx @ 1600', 50sx @ 800', 50sx @ 300', 10sx @ 40', 15sx in RH, 10sx in MH (total 235sx) of 60-40 poz, 6% gel. Completed @ 9:45 PM on 8-17-01.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Pickrell Drilling Company, Inc. License No. 5123

Address P.O. Box 1303 - Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co. Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Pickrell Drilling Company, Inc. (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact, statements, and matters herein contained and the log of the above described well as filed with the same are true and correct, so help me God.


(Signature) C. W. Sebits

(Address) C. W. Sebits, President
100 S. Main, Suite 505

Wichita, Kansas 67202-3738

SUBSCRIBED AND SWORN TO before me this 30th day of August 2001

Verdella Lewis
Notary Public



My Commission Expires: 6-06-2002

PICKRELL DRILLING COMPANY, INC.

100 SOUTH MAIN - SUITE 505

WICHITA, KANSAS 67202-3738

(316) 262-8427

RECEIVED

AUG 31 2001

#1 France "A"
195' S. of C E/2 SW
Section 15-18S-32W
Scott County, Kansas
Operator: Pickrell Drilling Co. Inc.

KCC WICHITA

Projected RTD: 4700'

API#: 15-171-20,564-0000
1125' From South Line of Section
3300' From West Line of Section
ELEV: 2985' KB, 2983' DF, 2980' GL
Contractor: Murfin Drlg. Co. Rig #3

- 8-06-01: MIRT & RURT.
- 8-07-01: (On 8-6) Spud @ 4:00 PM. Drilled 12 1/4" hole to 271'. Ran 7 jts. of New 8 5/8" 24# Csg. set @ 271', cmt w/175sx of common, 2% gel, 3% CC. Cmt circ. PD @ 9:45 PM on 8-6-01. WOC. (On 8-7) Started drlg. ahead @ 5:45 AM. Drlg. @ 300'.
- 8-08-01: Drlg. @ 1885'.
- 8-09-01: Drlg. ahead @ 2720'.
- 8-10-01: Drlg. ahead @ 3320'.
- 8-13-01: (On 8-11) Drlg. ahead @ 3857'. DST #1 3872-3900 (Oread) Straddle, 30"-60"-90"-90", Rec: 180' MW, 874' W. IFP 30-235#, ISIP 1115#, FFP 242-477#, FSIP 1114#. (On 8-12) GBIH after DST #1 3937'. (On 8-13) Circ @ 4003'. Prep to drill ahead after DST #2. DST #2 3950-4003, (LKC "A"), 30"-60"-90"-90", Rec: 240' MW. IFP 24-67#, ISIP 933#, FFP 68-144#, FSIP 876#.
- 8-14-01: Drlg. ahead @ 4190'. NOTE: Corrected Toronto and L/KC "A" tops. DST #3 3988-4016' (L/KC "B"), 30"-60"-30"-60", Rec: 25' WM (45% W, 55% M). IFP 19-30#, ISIP 1022#, FFP 30-40#, FSIP 987#. BHT 113 degrees.
- 8-15-01: Drlg. ahead @ 4316'. DST #4 4220-4250 (L/KC "J"), 30"-60"-30"-60", Rec: 15' WCM (30% W, 70% M). IFP 20-33#, ISIP 1043#, FFP 30-44#, FSIP 1007#.
- 8-16-01: Drlg. @ 4615'.
- 8-17-01: (On 8-16) Cke Sd 4607 (-1622), Miss 4629 (-1644). DST #5 4580-4645' (Miss): 30"-60"-30"-60", Rec: 10' M w/oil spots. IFP 30-34#, ISIP 1098#, FFP 41-48#, FSIP 936#. (On 8-17) RTD 4685'. LTD 4682'.
- 8-20-01: (On 8-17) P&A w/50sx @ 2330', 50sx @ 1600', 50sx @ 800', 50sx @ 300', 10sx @ 40', 15sx in RH, 10sx in MH (total 235sx) of 60-40 poz, 6% gel. Completed # 9:45 PM on 8-17-01. Final Report.

SAMPLE TOPS

Anhydrite	2313 (+ 672)
Base/Anhydrite	2331 (+ 654)
Topeka	3678 (- 693)
Heebner	3922 (- 937)
Toronto	3940 (- 955)
L/KC "A"	3966 (- 981)
Muncie Creek	4152 (- 1167)
L/KC "J"	4234 (- 1249)
Stark	4248 (-1263)
Hushpuckney	4287 (-1302)
B/Kansas City	4323 (-1338)
Pawnee	4463 (-1478) +6
Fort Scott	4508 (-1523) +4
Cherokee Shale	4529 (-1544) +5
Johnson Zone	4572 (-1587) +5
Cherokee Sand	4607 (-1622)
Mississippian	4629 (-1644)
RTD	4685'

ELECTRIC LOG TOPS

Heebner	3923 (- 938)
Lansing	3969 (- 984)
Stark	4248 (-1263)
Base/Kansas City	4325 (-1340)
Upr Pawnee	4462 (-1477)
Fort Scott	4504 (-1519)
Cherokee Shale	4528 (-1543)
Johnson Zone	4569 (-1584)
Mississippian	4631 (-1646)
LTD	4682'

ALLIED CEMENTING CO., INC.

7059

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Clarkley

DATE <u>8-17-01</u>	SEC. <u>15</u>	TWP. <u>18 S</u>	RANGE <u>32 W</u>	CALLED OUT	ON LOCATION <u>4:00 PM</u>	JOB START <u>7:15 PM</u>	JOB FINISH <u>9:45</u>
LEASE <u>France</u>	WELL # <u>A-1</u>	LOCATION <u>Scott City</u>	<u>3E-16N-14E</u>	COUNTY <u>Scott</u>	STATE <u>Kan</u>		
OLD OR NEW (Circle one)							

CONTRACTOR Mur Fin Dels Co #3

TYPE OF JOB PTA

HOLE SIZE 7 7/8 T.D. 4685'

CASING SIZE _____ DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE 4 1/2 x H DEPTH 2330'

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER Same

CEMENT

AMOUNT ORDERED 235 SKs 60/40 Poz
6% Gel, 1/4" # Flo-Soc

COMMON	<u>141</u>	SKs	@	<u>7.85</u>	<u>1,106.⁰⁰</u>
POZMIX	<u>94</u>	SKs	@	<u>3.55</u>	<u>333.⁰⁰</u>
GEL	<u>12</u>	SKs	@	<u>10.⁰⁰</u>	<u>120.⁰⁰</u>
CHLORIDE			@		
<u>Flo-Soc</u>	<u>59</u>	#	@	<u>1.40</u>	<u>82.⁰⁰</u>
			@		
			@		
			@		
			@		
HANDLING	<u>249</u>	SKs	@	<u>1.10</u>	<u>273.⁰⁰</u>
MILEAGE	<u>4¢</u>	per SK/mile			<u>9.76</u>
					<u>448.⁰⁰</u>
TOTAL					<u>2,060.⁰⁰</u>

EQUIPMENT

PUMP TRUCK CEMENTER Walt

300 HELPER Terry

BULK TRUCK

315 DRIVER Walt

BULK TRUCK

_____ DRIVER _____

REMARKS:

50 SKs @ 2330'

50 SKs @ 1600'

50 SKs @ 800'

50 SKs @ 300'

10 SKs @ 40'

15 SKs in R.H.

10 SKs in W.H.

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 630.⁰⁰

EXTRA FOOTAGE _____ @ _____

MILEAGE 45 miles @ 3.00 135.⁰⁰

PLUG 8 5/8 D.H. @ _____ 23.⁰⁰

_____ @ _____

_____ @ _____

TOTAL 788.⁰⁰

CHARGE TO: Pickrell Dels Co, Inc

STREET _____

CITY _____ STATE _____ ZIP _____

RECEIVED

AUG 31 2001

KCC WICHITA @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment
and furnish cementer and helper to assist owner or

TOTAL

ALLIED CEMENTING CO., INC. 4859

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley, KS

DATE <u>8-6-2001</u>	SEC. <u>15</u>	TWP. <u>8S</u>	RANGE <u>32 W</u>	CALLED OUT <u>2:30pm</u>	ON LOCATION <u>7:00pm</u>	JOB START <u>9:15pm</u>	JOB FINISH <u>10:00pm</u>
LEASE <u>France A</u>			WELL# <u>#1</u>	LOCATION <u>Scott City 36-114 N 6 W</u>		COUNTY <u>Scott</u>	STATE <u>KS</u>
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Murfin #3
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 271'
 CASING SIZE 8 5/8 24 DEPTH 271'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. 15'
 PERFS. _____
 DISPLACEMENT 16.2 BBLs

OWNER Pickrel
 CEMENT AMOUNT ORDERED 175 com 3% cc 290 gal

COMMON	<u>175</u>	@	<u>7.85</u>	<u>1373.25</u>
POZMIX		@	<u>10.00</u>	<u>30.00</u>
GEL	<u>3</u>	@	<u>30.00</u>	<u>180.00</u>
CHLORIDE	<u>6</u>	@		
		@		
		@		
		@		
		@		
HANDLING	<u>184</u>	@	<u>1.10</u>	<u>202.40</u>
MILEAGE	<u>45</u>	@	<u>4.44/1K</u>	<u>331.20</u>
TOTAL				<u>2117.30</u>

EQUIPMENT

PUMP TRUCK # 300 CEMENTER Fuzzy
 HELPER Wayne
 BULK TRUCK # 218 DRIVER Jarrod
 BULK TRUCK # _____ DRIVER _____

REMARKS:

Mix & pump 175 com 3% cc 290 gal
displace plug to within 15'
at Bottom
Cement did circulate
Plug down @ 9:45pm
 Thanks
 Fuzzy

SERVICE

DEPTH OF JOB	<u>271</u>		
PUMP TRUCK CHARGE			<u>520.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>45</u>	@	<u>3.00</u> <u>135.00</u>
PLUG	<u>8 5/8</u>	@	<u>45.00</u> <u>45.00</u>
		@	
		@	
TOTAL			<u>700.00</u>

CHARGE TO: Pickrel
 STREET _____
 CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

RECEIVED	@	
AUG 31 2001	@	
KCC WICHITA	@	

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment

TOTAL _____