

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-171-20,236-0000
~~774~~

LEASE NAME Beckley

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div. C
 office within 30 days.

WELL NUMBER 1

NE NW/4 Ft. from S Section Line

Ft. from E Section Line

LEASE OPERATOR Petro Dynamics Corporation

SEC. 26 TWP. 18 RGE. 32 (#) or (W)

ADDRESS 1650 Georgetown Suite 200 Wichita, Ks. 67218

COUNTY Scott

PHONE# (316) 681-1685 OPERATORS LICENSE NO. 5053

Date Well Completed 8-14-82

Character of Well oil

Plugging Commenced 4-25-85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-27-85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed? no If not, is well log attached? N/A

Producing Formation Miss Depth to Top _____ Bottom _____ T.D. 4668

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	334	8 5/8		
		0	4668	4 1/2		1859

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

fill with sand to 4560 & dump 4 sxs. cement

Pump 8 5/8 with 2 hulls- 15 gal 50 cement 10 gal 1 sx. hulls & plug then 125 sxs. cement used 50/50 pozmix 2% gel & 3% c.c. Allied cementing Co. Inc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Nicholas Casing Pulling License No. 6698

Address Box 108 Geneseo, Ks/ 67444

STATE OF Kansas COUNTY OF Rice, ss.

Allen D. Nicholas (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

STATE CORPORATION COMMISSION

(Signature) Allen D. Nicholas

(Address) _____

MAY 01 1985
 5-1-85

SUBSCRIBED AND CONFIRMED me this 30th day of April, 19 85

Wichita, Kansas

Joni L. Prickett
 Notary Public

My Commission Expires: December 25, 1988



PETRO



DYNAMICS CORP

15171-20236-0000

DAILY DRILLING REPORT

PDC BECKLEY #1
C NE NW/4 SEC. 26-18S-32W
SCOTT COUNTY, KANSAS
GL: 2965'
KB: 2973'
CONTRACTOR:

COMPARISON WELL:
IMPERIAL #1 NEWBY
SEC. 23-18S-32W
SCOTT COUNTY, KANSAS
KB: 2973'

7/25/82 M.I. & R.U. C NE NW/4 Sec. 26,
T18S-R32W, Scott Co., KS. Elevations: G.L. 2965', K.B. 2973'.

7/26/82 RTD 650'. Drilling. TPFH 650'. Day #1. Spud @ 8:30 a.m., 7/25/82.
Drilled 12 1/4" hole to 335'. Ran 8 jts (323'), L.B. Foster 8 5/8" 23 lb
X-42 csg to 334' & cemented w/205 sx Class A (2% gel, 3% CaCl₂); cement
circulated w/plug down @ 2:30 p.m., 7/25/82. Nipple up & start drilling
7 7/8" hole @ 10:30 p.m.

*this is all the info I have on this
well*

FEB 11 1985

CONSERVATION DIVISION
Wichita, Kansas

~~2108505~~