

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-171-20132-0000

API NUMBER NA

LEASE NAME Lay

WELL NUMBER 1-25

SPOT LOCATION C SW

SEC. 25 TWP. 18 RGE. 32 (X) or (W)

COUNTY Scott Co., Ks.

Date Well Completed 3-13-77

Plugging Commenced 8-18-1988

Plugging Completed 8-25-1988

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Methanol Production Corp.

ADDRESS 165 So. Union Ste.; Suite 500; Lakewood, CO 80228

PHONE # (303) 908-1277 OPERATORS LICENSE NO. 4311

Character of Well Gas  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing formation Krider Depth to top 2768 bottom 2774 T.D. 2819

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface				8 5/8"	382'	0'
Production				4 1/2"	2819'	500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls and 20 sks. cement to 2640' - pressured to 750 lbs.

Pulled 4 1/2" into at 500'

Allied cementing pumped 200 sks. of ATL cement down 8 5/8"

Cut off 8 5/8", 3' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497  
Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I Edgar J. Eves

(~~Operator~~) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877

SEP 22 1988  
9-22-88  
CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 31st day of August, 1988

Sandra L. Eves  
Notary Public

My Commission expires: 12-6-88



# CAR-REN

114 645 - R. H. Garvey Building  
300 West Douglas  
Wichita, Kansas 67202  
316/264-5406

FEB 7 1977

Lay 1-25  
C SW 1/4 25-18S-32W  
Scott County, Kansas

Contractor: Gabbert-Jones, Inc.  
Geologists: W. Walter Scott and  
Charles R. King

Elevations: 2974 GL  
2979 RB

15-171-20132-0000

1-25-77 Spud 10:30 a.m. Drilled 12 1/2" hole to 395'. Ran 9 joints 8 5/8", 28#,  
used casing. Total tally 376.63'. Set at 382' with 265/sx Class H,  
3% CaCl. Cement circulated to surface. PD at 5:30 - .m. WOC

1-27-77 Drilling at 2310.  
Sample Top:

1-28-77	Stone Corral	2240 (+739)
	Base Stone Corral	2305 (+674)
	Herington	2739 (+240)
	Krider Dolomitic Sandstone	2764 (+215)

Logging. 2799' TD

Petro-Log tops:

Stone Corral	2242 (+737)
Base Stone Corral	2304 (+675)
Herington	2736 (+243)
Krider	2760 (+219)
RTD	2820
LTD	2798

Preparing to take DST #1. 4 to 6' of gas effect from 2766 - 2772.

DST #1 2739 - 2799

Open 10" Shut in 20" Open 120" Shut in 150"

GTS 21"

Rec: 240' GCM

IFP's 86 - 56

IBHCIP 512

FFP's 64 - 104

IHH 1438

FBHCIP 525

FHH 1458

Gauges:

10"	8,870	CFGPD
20"	12,500	"
30"	15,400	"
40"	16,700	"
50"	17,200	"
60"	18,800	"
70"	20,900	"
80"	21,900	"
90"	21,900	"
100"	22,800	"
110"	22,800	"

1-29-77 Ran 70 joints 4 1/2", 9.5# ERW casing. Total tally 2820.36 set at 2819',  
cemented with 125/sx 50-50 pozmix, 10% salt, 3/4% CFR-2. Good circula-  
tion. PD at 1:05 p.m.