

4-061170

9-9

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-00,006-0001

C NW SE /4 SEC. 09, 14 S, 42 W
1980 feet from S section line
1980 feet from E section line

Operator license# 9860

Lease: Goodrich Well # 1

Operator: Castle Resources, Inc.

County: Wallace 63.38

Address: Box 87
Schoenchen, Kansas 67667

Well total depth 1950 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 441 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Plains, Inc. License# 4072

Address: Ness City, Kansas 67560

Company to plug at: Hour: A.M. Day: 9 Month: September Year: 1998

Plugging proposal received from: Jerry Green

Company: Castle Resources, Inc. Phone: 785-625-5155

Were: Order 145 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy mud through tubing.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour A.M., Day: 9, Month: September, Year: 1998

Actual plugging report: 8 5/8" set to 441'. Attempted to re-enter old hole. Ran into junk and debris and finally stopped at 1950'. Decision to D&A. Ran tubing to 1778' and pumped 80 sxs cement. Pulled tubing to 490' and pumped 40 sxs cement. Pulled tubing to 40' and pumped 10 sxs cement. 10 sxs cement in rathole.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X
Bottom plug(in place): YES, CALC X, NO
Anhy.plug: YES NO
Dakota plug: YES
Elevation: 3850 GL

I did[] / did not[X] observe the plugging.

[Signature]
(agent)
AH

Form CP-2/3

11-24-1998

DEC 01 1998

60385