

205R

6 070924

API NUMBER 15- 199-20,199-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NW SW, SEC. 6, T 14 S, R 42 W/EX
2200 feet from S section line
4380 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3771
Operator: E.P. Operating Co.
Name & Address: 4849 Greenville Ave. 31200
Dallas, Tx. 75206
Jack L. Sledge

Lease Name Stegman A Well # G #1
County Wallace 172.25
Oil Total Depth 5300 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 654

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number _____
Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 22 Month: May Year: 19 91

Plugging proposal received from Ed Mckenna

(company name) Murfin Drilling Co. (phone) _____

were: 8 5/8 654 ft. s.p. cwc w/350 sks 60/40 poz 6% gel 3 cc. By Allied Cement.
Morrow well. Elv. 3875 Anhy 2871. Mud cond 52 vis 9.2 wt. 8 w.l.

Proposal 220 sks 60/40 poz 6% gel 3% ca cl. Circulate hole. Spot with
drill stem, heavy mud between all pugs. 25 sks at 2880 ft. 100 sks w/1 sk
f.c. at 1920. 60 sks at 675 ft. 10 sks at 40 ft. 15 sks in rathole.
10 sks mouse hole. Circulated.

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 9:00AM Day: 22 Month: May Year: 19 91

ACTUAL PLUGGING REPORT Murfin ordered 220 sks 60/40 poz 6% gel and 1
sks f.c. circulated hole. Spotted and displaced cement through drill pipe.

- 1st plug at 2880 w/25 sks cement
- 2nd plug at 1920 w/100 sks cement 1 sk f.c. 15 sks rathole Circ.
- 3rd plug at 675 w/60 sks cement 10 sks mousehole. Circ. Allied Cement Ness City.
- 4th plug at 40 w/10 sks cement.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-5-91
INV. NO. 32001

Sub. S

Signed Marion J. Schmidt
(TECHNICIAN)
Marion J. Schmidt

RECEIVED
STATE CORPORATION COM
MAY 30 1991
05-30-1991
CONSERVATION DIVIS
Wichita, Kansas