

4-060468

11-15

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-109-20,559-00-00

W2 SE NE /4 SEC. 05, 15 S, 33 W  
3300 feet from S section line  
990 feet from E section line

Operator license# 3581 Lease Staats well # 1-5

Operator: Red Oak Energy, Inc. County Logan

Address: 200 W. Douglas #510 Well total depth 4525 feet  
Wichita, Kansas 67202 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 220 feet

147.06

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD \_\_, D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:00P.M. Day: 15 Month: November Year: 93

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: 913-483-3518

Were: Order 190 sxs. 60/40 posmix - 6% gel with 1/4# flocele per. sx.  
Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 7:00P.M., Day: 15, Month: November, Year: 93

Actual plugging report:  
1st. plug at 2225' w/25 sxs. - Anhydrite 2219' - 2238'.  
2nd. plug at 1005' w/100 sxs. - Dakota 702' - 1002'.  
3rd. plug at 270' w/40 sxs. - Surface pipe to 220'.  
4th. plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Remarks: Cement by: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: 2802 GL

I did [ ] did not [ X ] observe the plugging.

*[Signature]*

DA (agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 01 1993  
12-01-1993  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED  
DATE 12-8-93  
INV. NO. 39435