

4-020079

5-19

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-109-20,678-0000

NE SW SE /4 SEC. 30, 15 S, 32 W
990 feet from S section line
1650 feet from E section line

Operator license# 5135

Lease: Fairleigh Ranch Well # 1

Operator: John O. Farmer, Inc.

County: Logan 151.19

Address: P.O. Box 352
Russell, Kansas 67665

Well total depth 4652 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 221.7 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling License# 31548

Address: P.O. Box 763 - Hays, Kansas 67601-0763

Company to plug at: Hour: 7:30 A.M. Day: 19 Month: May Year: 1999

Plugging proposal received from: Tom Alm

Company: Discovery Drilling Phone: 785-623-2920

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Jay Pfeifer
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour 10:30 A.M., Day: 19, Month: May, Year: 1999

Actual plugging report: 8 5/8" set at 221.7' w/150 sxs cement.
1st. Plug at 2250' w/25 sxs.
2nd. Plug at 1150' w/100 sxs.
3rd. Plug at 275' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2846 GL

I did[] / did not[X] observe the plugging.

Jay Pfeifer
(agent)
Form CP-2/3

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

DATE 5-25-99

MAY 24 1999
0524-1999

INV. NO. 60985

CONSERVATION DIVISION
Wichita, Kansas