

9-21-87

To: 6 070599  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,111-00-00  
irregular sec.  
SW, SEC. 25, T 14 S, R 43 W/E  
330 feet from S section line  
approx 1620 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5171  
Operator: TXO Production Corp  
Name & Address: 155 North Market #1000  
Wichita, Kansas 67202  
Cory West

Lease Name Purvis Farms Well # 1-25  
County Wallace  
Well Total Depth 5300 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 670

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling Inc. License Number 5107  
Address Wichita, Kansas 67601

Company to plug at: Hour: 7:00 PM Day: 21 Month: Sept Year: 19 87

Plugging proposal received from Allen Dick

(company name) H-30 Drilling Inc. (phone) 316-269-7655

were: 8 5/8" 670' SP cwc w/300 sks cement. By B. J. Titan.

Elevation 3930', Anhy 2628', Miss Well, No Circulation problems.

Mud 92 weight, 50 Vis. 8.8 water loss. Proposal 220 sks 60/40 Pozmix

6% Gel 3% Ca Cl 1 sk Celloflake. Spot with drill stem, recondition hole.

Mud between all plugs; 25 sks at 2820' 100 sks at 1830'; 40 sks at 700';

20 sks at 300'; 10 sks at 40'; 15 sks in rat hole; 10 sks in mouse hole.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 7:00 PM Day: 21 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Ordered 220 sks 60/40 Pozmix 6% Gel 3% Ca Cal, 1 sk Celloflake and 8 5/8" plug. Spotted with drill stem. Heavy mud between plugs. 1st plug at 2820' w/ 25 sks cement; 2nd plug at 1830' w/100 sks cement w/1 Flake; 3rd plug at 700' w/40 sks cement; 4th plug at 300' w/20 sks cement; 5th plug Hulls and plug at 40' w/10 sks cement; 15 sks in rat hole (circulated); 10 sks in mouse hole (circulated). Cemented by B. J. Titan.

RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas

OCT 23 1987  
10-23-87

Remarks: (If additional description is necessary, use BACK of this form)

INVOICED  
DATE 10-26-87  
INV. NO. 18676

Signed Marion J. Schmidt (TECHNICIAN)