

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-199-20, 047-00-00

C-SE, SEC. 19, T 15S, R 38WE

1320 FEET FROM N(S) SECTION LINE

1320 FEET FROM W(E) SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5005

LEASE NAME LINDER WELL # "B"-1

OPERATOR: SUNBURST EXPLORATION  
NAME & ADDRESS ONE MAIN PLACE #708  
WICHITA, KS. 67202

COUNTY WALLACE \$1 172.09

WELL TOTAL DEPTH 5295 FEET

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 13 3/8 FEET 324

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A X

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR BLUE GOOSE DRUG. CO LICENSE NUMBER 5104

ADDRESS P.O. BOX 1412, GREAT BEND No. 67530

COMPANY TO PLUG AT: HOUR: 6:00 AM DAY: 21st MONTH: AUG. YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM LEROY BARRON

(COMPANY NAME) BLUE GOOSE DRUG. (PHONE) 316-262-3041

WERE: 13 3/8" - 324 FT SP. CUL #/400 ST COMMON - 2% GEL - 3% CA-CL. (BY SUN)  
ORDER 355 ST 50 Formix 6% GEL - 3% CA-CL. AND 13 3/8" Plug.  
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS  
NO HERRUCKLE - EV. 3535' ANHY. 2617.

PLUGGING PROPOSAL RECEIVED BY Marion Schmidt  
(TECHNICIAN) OOIC

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL \_\_\_\_\_ PART \_\_\_\_\_ NONE X

OPERATIONS COMPLETED: HOUR: 6:30 AM DAY: 21st MONTH: AUG. YEAR: 19 83

ACTUAL PLUGGING REPORT

13 3/8" - 324 FT SP. CUL #/400 ST COMMON - 2% GEL - 3% CA-CL. (BY SUN CMT)  
ORDERED 355 ST 50 Formix 6% GEL - 3% CA-CL. AND 13 3/8" Plug  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1st Plug @ 2640 FT #/40 ST CMT., 2nd Plug @ 1620 FT #/200 ST CMT.  
3rd Plug @ 330 FT #/75 ST CMT., 4th Plug <sup>SOLID BRIDGE</sup> NULL'S PLUG @ 40 FT #/20 ST CMT.

REMARKS: (CEMENTED BY SUN - CMT.) - 10 ST IN BAT HOLE, - 10 ST IN WATER WELL.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 29 1983 08-29-83

CONSERVATION DIVISION  
Wichita, Kansas

I ( ~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Marion Schmidt  
(TECHNICIAN) OOIC

INVOICED  
DATE 8-31-83  
INV. NO. 5392-W

FORM CP-213  
27 REV. 6-83