

12-14

6 031210

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,167-00-00

SW SW NW, SEC. 9, T 15 S, R 40 W/E

2970 feet from S section line

4950 feet from E section line

Lease Name SSilkman Well # 5-9

County Wallace 169.98

Well Total Depth 5230 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 393

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655

Operator: BHP Pet. Americas Inc.

Name & Address 5613 DTC Parkway Suite 600

Englewood, Co. 80111

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling License Number

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 14 Month: Dec Year: 19 88

Plugging proposal received from Steve Carlton

(company name) Murfin Drilling (phone)

were: 8 5/8" set at 393' w/cwc circ. hole w/no less than 36 vis mud w/no loss

or gain of fluids. Balance plugs w/mud. Order 190 sks 60/40 Poz 6% Gel 3% CaCl 8 5/8"

wiper plug. B. J. Titan Cement Co.

RECEIVED
STATE CORPORATION COMMISSION
01-18-89
18 1989

Plugging Proposal Received by Carl Goodrow

(TECHNICIAN)

x

Plugging Operations attended by Agent?: All Part None

Operations Completed Hour: 3:00Pm Day: 14 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT

Spot plugs w/drill pipe at 2725' w/25 sks

2000' w/100 sks w/Hulls

440' w/40 sks

40' w/10 sks

15 sks in rathole.

Remarks: Anhy. 2714' - 39'

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE 1-19-89

INV. NO. 23673

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow