

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-199-20,046-00-00

NE, Sec. 4, T 15 S, R 40 W E

1890 feet from N/S section line

1800 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7506

Lease Name PERRY Well # 32-4

Operator: FIRST ENERGY CORP.
Name & Address P.O. BOX 2066
JACKSON, MS.
39205

County WALLACE

Well Total Depth 5090 feet \$165.43

Conductor Pipe: Size 0 feet

Surface Casing: Size 10 3/4 feet 359 ✓

Abandoned Oil Well ___ Gas Well ___ Input Well ___ SWD Well ___ D&A X

Other well as hereinafter indicated

Plugging Contractor MURFIN DRILG. Co License Number 6033

Address 617 UNION CTR. BLDG. WICHITA, KANS. 67202

Company to plug at: Hour: 8:00 PM Day: 13th Month: MAY Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO TERRY Mc CRAW

(company name) MURFIN DRILG. Co (phone) 601-944-1000

were: 10 3/4" - 359th SP. CUL. 1/250th, 60/140 Pozmix - 3% CA-CL. (By SUN/OMT)

ORDER 250th 50/150 Pozmix 6% GEL - 3% CA-CL. AND 8 5/8" Plug

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

NO ARDUABLE. ELV. 3646 ANH. 2709.

Signed *Morgan Schmidt*
(TECHNICIAN) (DOLC)

Plugging Operations attended by Agent?: All ___ Part ___ None X

Operations Completed: Hour: 8:00 PM Day: 13th Month: MAY Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 250th 50/150 Pozmix 6% GEL - 3% CA-CL. AND 8 5/8" Plug

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 2730th EI 1/25th CNT., 2nd Plug @ 1650th EI 1/100th CNT.

3rd Plug @ 360th EI 1/90th CNT. 4th Plug ^{SOLID BRIDGE} HALL'S - Plug @ 40th 1/15th CNT.

10th IN RAT HOLE (CIR.) 10th IN MOUSE HOLE (CIR.)

Remarks: CEMENTED BY SUN OMT

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed *Morgan Schmidt*
(TECHNICIAN) (DOLC)

RECEIVED
STATE CORPORATION COMMISSION

MAY 20 1983

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 5-23-83

INV. NO. 4397-W