

4 060045

12-8

249

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-199-20,182-00-00

S2 SE NW, SEC. 7, T 14 S, R 41 W/EX

2973 feet from S section line

3394 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Reiss 22-1 Well # 1

Operator: Union Pacific Resources Company

County Wallace 172.41

Name & Address P.O. Box 7 MS 3407

Well Total Depth 5305 feet

Fort Worth, Texas 76101-0007

Conductor Pipe: Size \_\_\_\_\_ feet

817-877-7956

Surface Casing: Size 8 5/8 feet 523

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling Co License Number 6033

Address Wichita, KS

Company to plug at: Hour: 9:45AM Day: 8 Month: December Year: 19 89

Plugging proposal received from Bobby Cooper

(company name) Union Pacific Resources Company (phone) 817-877-7956

were: Space all plugs with heavy drilling mud through drill pipe.

Order 200 sxs. 60/40 pos 6% gel w/ floccel per sx.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXXXX

Operations Completed: Hour: 9:45 AM Day: 8 Month: December Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2860' with 25 sxs. Anhydrite 2842-2872'

2nd plug at 1890' with 100 sxs. Dakota 1589-1889'

3rd plug at 575' with 40 sxs. Surface pipe to 523'

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs. mousehole with 10sxs. RECEIVED  
STATE CORPORATION COMMISSION

Arbuckle not reached

JAN 17 1990

Remarks: B-J Titan

(If additional description is necessary, use BACK of this form) CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

(If additional description is necessary, use BACK of this form) CONSERVATION DIVISION  
Wichita, Kansas

DATE JAN 26 1990

Signed Herb Deines  
(TECHNICIAN)

INV. NO. 27162

12-8 FEB 05 1990