

12-19

6 070816

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 199-20,181-00-00.
S/2 SE NE, SEC. 7, T 14 S, R 41 W&E
2973 feet from S section line
620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Reiss 41-7 Well # 2

Operator: Union Pacific Resources Co.
Name & Address: Box 7 MS 3407

County Wallace 174.07

Fort Worth, Texas 76101-0007

Well Total Depth 5356 feet

Joy L. Prohaska

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1004

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number

Address Wichita, Ks. 67202

Company to plug at: Hour: AM Day: 19 Month: Dec Year: 19 89

Plugging proposal received from Bob Cooper

(company name) Union Pacific Resources (phone)

were: 8 5/8" s.p. 1004' cwc w/535' 65/35 poz 6% gel 3% cal cl. By B. J. Titan.

Miss. well. Elevation 3778'. Anhy 2840' No circulation problems. Mud condition
viscosity 55 - weight 9.0 water loss 8. Proposal 230 sks 60/40 poz 6% gel and w/1 sks
f.c. Spot with drill stem, circulate heavy mud between all plugs. 30 sks at 2850' - 100 sks

at 1875' - 40 sks at 1050' - 25 sks at 400' 10 sks at 40' w/plug. 15 sks rathole 10 sks h
mousehole, Circulate. Plugging Proposal Received by *Marion Schmidt*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30AM Day: 19 Month: Dec. Year: 19 89

ACTUAL PLUGGING REPORT Pacific ordered 230 sks 60/40 poz 6% gel and 8 5/8" plug. Circu-
lated hole - spotted cmeent with drill stem with heavy mud between all plugs.

1st plug at 2850' w/30 sks cement. 2nd plug at 1875' w/100 sks w/1 sl f.c.

3rd plug at 1050' w/40 sks cement.

4th plug at 400' w/25 sks cement. 5th plug at 40' w/plug w/10 sks cement

15 sks rathole (circulate)

10 sks mousehole (circulate)

Remarks: (If additional description is necessary, use BACK of this form.)

I (XXXXXX) did not observe this plugging.

INVOICED
DATE JAN 26 1990

INV. NO. 27163

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1990
CONSERVATION DIVISION
Wichita, Kansas
Signed *Marion Schmidt*
(TECHNICIAN)
Marion J. Schmidt

12-19 FEB 05 1990