

6-150176

40-22

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-199-20,231-00-00

NW NE NW /4 SEC. 30, 15 S, 41 W
330 feet from N section line
1656 feet from W section line

Operator license# 3581 Lease Phelps well #1-30

Operator: Red Oak Energy, Inc. County Wallace

Address: 200 W. Douglas, Suite 510 Well total depth 5250 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 351 feet

170.63

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Murfin Drilling License# 5144

Address: Wichita, Kansas

Company to plug at: Hour: AM Day: 22 Month: October Year: 1995

Plugging proposal received from: Berny Meyer

Company: Murfin Drilling phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2800 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1790 feet " 100 " Mousehole: 10 sacks

3rd plug @ 400 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:30 AM, Day: 22, Month: October, Year: 1995

Actual plugging report: Hole reported plugged as above.
Order 190 sx 60/40 pozmix w/ 6% gel and 1/4 lbs sx celloflake or flowcel
per sx of cement.

Remarks: Elevation: 3835 GL, Anhydrite depth: 2791 - 2808 feet

Did not penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

Bruce Basye
Bruce D. Basye, Geologist
(agent)
Form CP-2/3

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 20 1995
12.20.95
CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 1-4-96

INV. NO. 44366