

12-2
4-050181

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-199-20,211-00-00
SW SE SE /4 SEC. 30, 15 S, 41 W
330 feet from S section line
1000 feet from E section line

Operator license# 30606 Lease Nikrbash well #1-30

Operator: Murfin Drilling Company Inc County Wallace

Address: 250 N. Water Suite 300 Well total depth 5300 feet
Wichita, Kansas 67202 Conductor Pipe: inch @ feet
(316)267-3241 Surface pipe 8 5/8 inch @ 388 feet

172.25

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Murfin Drilling Company Inc. License#

Address:

Company to plug at: Hour: PM Day: 02 Month: December Year: 1993

Plugging proposal received from: Gus Schwartz

Company: Murfin phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2760 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1755 feet " 100 " Mousehole: 10 sacks

3rd plug @ 440 feet " 40 "

4th plug @ 40 feet " 10 " with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 8:30 PM, Day: 02, Month: December, Year: 1993

Actual plugging report: Hole reported plugged as above.

Order 200 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

Remarks: Elevation: 3806, Anhydrite: 2743-2772 feet, Anhydrite plug: 2760
Bottom plug (in place): Yes X, Calc , No Arbuckle: None

RECEIVED
STATE CORPORATION COMMISSION
DEC 08 1993

Did NOT penetrate Arbuckle, cemented by Allied Cementing Company

I did / did not X observe the plugging. Marvin L. Miller

CONSERVATION DIVISION
Wichita, Kansas

Marvin L. Miller P.I.R.T.II
(agent)

INVOICED

DATE DEC 14 1993

INV. NO. 39516

12-02