

6 - 010776

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-199-20,206-0000

SWNWSW / 4 SEC. 30, 15 S. 41 W  
1650 feet from S section line  
330 feet from E section line

Operator license# 30606

Lease Black Pony well # 1-30

Operator: Murfin Drilling Co.

County Wallace

Address: 250 North Water  
Suite 300  
Wichita, Ks. 67202

Well total depth 5350 feet  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 inch @ 358 feet

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Murfin License# 30606

Address: Wichita

Company to plug at: Hour:        Day: 14 Month: January Year: 92

Plugging proposal received from: Rodney Farr

Company: Murfin phone:       

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

Order 200 sks cement 60/40 poz 6% gel and 2 sks f.c.

1st plug @ 2760 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1700 feet " 100 " Mousehole: 10 sacks

3rd plug @ 380 feet " 40 "

4th plug @ 40 feet " 10 "

5th plug @        feet " wiper plug & 10sx

Plugging Proposal Received by: Dale Balthazor

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 2:15AM, Day: 14, Month: January, Year: 92

Actual plugging report: 25 sks at 2760

100 sks at 1700

40 sks at 380

Allied Cement Co. 10 sks at 40 15 sks rathole 10 mousehole.

Remarks: Elevation: 3802 GL, Anhydrite depth:        -        feet

Anhy. plug: YES Dakota plug: YES Bottom hole plug in place: YES

Plugged through drill pipe: YES

Did        penetrate Arbuckle, cemented by       

**INVOICED**

I did[        ] did not[ X ] observe the plugging

DATE 2-18-92

INV. NO. 34582

Dale Balthazor  
Dale Balthazor  
(agent)

Form CP-2/3