

4-070162

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-199-20,281-0000

W2 NW NE NE /4 SEC. 30, 15 S, 41 W
4950 feet from S section line
1225 feet from E section line

Operator license# 31881

2/21

Lease: Kriegh Well # 1-30

Operator: McGinness Oil Company of Kansas

County: Wallace 172.25

Address: 150 N. Main - Suite 1026
Wichita, Kansas 67202

Well total depth 5300 feet
Conductor Pipe: 0 inch @ 0 sxs.
Surface pipe 8 5/8 Inch @ 383 feet

ABAND. oil well , Gas well , Input well , SWD. , D&A

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - #300 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 21 Month: February Year: 2000

Plugging proposal received from: Keith VanPelt

Company: Murfin Drilling Company, Inc. Phone: 719-537-0314

Were: Ordered 200 sxs 60/40 pozmix - 6% gel - 1/4 Floseal per sack. One 8 5/8" wiper plug.
Spot plugs through drill pipe with heavy drilling mud between all plugs.

Plugging Proposal Received by: Rich Williams
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 5:15 P.M. Day: 21, Month: February, Year: 2000

Actual plugging report: No ar buckle cut.

1st Plug 2767' w/25 sxs. Anhydrite 2752' - 2781'.

2nd Plug 1760' w/100 sxs. Dakota Base 1460' - 1760'.

3rd Plug 433' w/40 sxs. Surface pipe 383' + 50'

4th Plug 40' w/10 sxs. One 8 5/8" wiper plug.

Rathole w/15 sxs.

Mousehole with 10 sxs.

Remarks: _____

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 3810 GL

I did[] / did not[] observe the plugging.

Richard Williams
(agent)

INVOICED

DATE 2/28/00

INV. NO. 061307

RECEIVED CP-2/3
STATE CORPORATION COMMISSION

FEB 24 2000

CONSERVATION DIVISION
Wichita, Kansas

(Handwritten signature/initials)