

4-050197

7-25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-199-20,220-00-00

E2 E2 /4 SEC. 26, 15 S, 41 W  
2640 feet from N section line  
490 feet from E section line

Operator license# 30606

Lease Akers Trusts well # 1-26

Operator: Murfin Drilling Company, Inc.

County Wallace

Address: 250 N. Water  
Suite #300  
Wichita, Kansas 67202

Well total depth 5350 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 370 feet

173.88

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Murfin Drilling Company, Inc. License# 30606

Address: 250 N. Water - Suite #300 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 25 Month: July Year: 94

Plugging proposal received from: Jim Renner

Company: Murfin Drilling Company, Inc. Phone:                     

Were: Order 200 sxs. 60/40 pozmix - 6% gel - 1/4# flocele.  
Spot plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Marvin Miller

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 4:00P.M., Day: 25, Month: July, Year: 94

Actual plugging report:

1st. plug @ 2740' w/25 sxs.

2nd. plug @ 1670' w/100 sxs.

3rd. plug @ 420' w/40 sxs.

4th. plug @ 40' w/10 sxs.

15 sxs. in rathole.

10 sxs. in mousehole.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD      BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING     . Elevation: 3717

RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1994

08-11-94

CONSERVATION DIVISION  
WICHITA, KANSAS

I did      / did not X observe the plugging.

Marvin Miller  
(agent)

INVOICED

DATE 8-24-94

INV. NO. 40966