

4-25

263

6 031357

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 199 20 185-00-00
SE SE SE, SEC. 9, T 15 S, R 41 W/E

330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Koehn Farms Well # 44C-9 #1

Operator: Union Pacific Resources Co.

County Wallace 174-69

Name & Address Box 7 MS 3407

Well Total Depth 5375 feet

Fortworth, Texas 76101 - 0007

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 621

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Rains and Williamson License Number 5146

Address Wichita, Ks

Company to plug at: Hour: AM Day: 25 Month: April Year: 19 90

Plugging proposal received from Bob Casper

(company name) Rains and Williamson (phone)

were: 8 5/8" set at 621' w/350 sks cwc. Circ hole w/no less than 36 vis mud w/no loss or gain of fluids. Keep hole full of and balance plugs w/mud.

Order. 200 sks 60/40 poz 6% gel 3% cal cl 8 5/8" plug. Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:00 AM Day: 25 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2740' w/25 sks

1700' w/100 sks and hulls

670' w/40 sks

40' w/10 sks

Circ 15 sks in rathole Circ 10 sks in mousehole

Remarks: Elev. 3739 Anhy 2738 - 68

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-9-90

MAY 07 1990
05-07-90
CONSERVATION
Wichita, Kansas
Jub. S

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

WV. NO. 28101 JUN 21 1990