

15-171-20379-00-00

FORM MUST BE TYPED  
FORM C-1 12/88

State of Kansas  
NOTICE OF INTENTION TO DRILL

FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date ... February 14 1989 ...  
month day year  
SW. NW. NE. Sec 12. Twp 16 S, Rg 31 East West

OPERATOR: License # 3988  
Name: SLAWSON EXPLORATION COMPANY, INC.  
Address: 104 South Broadway  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Bob Jenkins  
Phone: (316) 263-3201

4240' FSL ... feet from South line of Section  
2260' FEL ... feet from East line of Section  
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 6039  
Name: L. D. Drilling, Inc.

County: Scott  
Lease Name: YORK "BZ" Well #: 1  
Field Name: Wildcat  
Is this a Prorated Field? ... yes X no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 2836' GR (Seis) feet MSL  
Domestic well within 330 feet: ... yes X no  
Municipal well within one mile: ... yes X no  
Depth to bottom of fresh water: 150'  
Depth to bottom of usable water: 1200'  
Surface Pipe by Alternate: ... 1 X 2  
Length of Surface Pipe Planned to be set: 280'  
Length of Conductor pipe required: None  
Projected Total Depth: 4550'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations:  
... well X farm pond ... other  
DWR Permit #: ...  
Will Cores Be Taken?: ... yes X no  
If yes, proposed zone: ...

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Inj ... Infield X Mud Rotary  
... Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWMO ... Disposal X Wildcat ... Cable  
... Seismic; ... # of Holes

If OWMO: old well information as follows:  
Operator: ...  
Well Name: ...  
Comp. Date: ... Old Total Depth ...

Directional, Deviated or Horizontal wellbore? ... yes X no  
If yes, total depth location: ...

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

It is agreed that the following minimum requirements will be met:

- 1. The appropriate district office shall be notified before setting surface pipe;
- 2. The minimum amount of surface pipe as specified above shall be set by circulating cement to the top; in all cases surface pipe shall be set through all unconsolidated materials plus a minimum of 20 feet into the underlying formation;
- 3. If the well is dry, a plugging proposal shall be submitted to the district office. An agreement between the operator and the district office on plug length and placement is necessary prior to plugging;
- 4. The appropriate district office will be notified before well is either plugged or production casing is cemented in;
- 5. If an Alternate II completion, production pipe shall be cemented from below any usable water to surface within 120 days of spud date. In all cases, notify district office prior to cementing.

I hereby certify that the statements made herein are true and to the best of my knowledge and belief. Western Kansas  
Date: 2/9/89 ... Signature of Operator or Agent: Robert B. Jenkins Title: District Geologist

5280		5280
4950		4950
4620		4620
4290		4290
3960	X	3960
3630		3630
3300		3300
2970		2970
2640		2640
2310		2310
1980		1980
1650		1650
1320		1320
990		990
660		660
330		330

RECEIVED  
STATE GEOLOGICAL COMMISSION  
FEB 9 1989  
CONSERVATION DIVISION  
Wichita, Kansas

FOR KCC USE:  
API # 15- 171-20,379-0000  
Conductor pipe required \_\_\_\_\_ feet  
Minimum surface pipe required 200' feet per Alt. X 2  
Approved by: LUM 2-9-89  
EFFECTIVE DATE: 2-14-89  
This authorization expires: 9-9-89  
(This authorization void if drilling not started within 6 months of effective date.)  
Spud date: \_\_\_\_\_ Agent: \_\_\_\_\_

18  
16  
31W

- REMEMBER TO:
- File Drill Pit Application (form CDP-1) with Intent to Drill;
  - File Completion Form ACO-1 within 120 days of spud date;
  - File acreage attribution plat according to field proration orders;
  - Notify appropriate district office 48 hours prior to workover or re-entry;
  - Submit plugging report (CP-4) after plugging is completed;
  - Obtain written approval before disposing or injecting salt water.