

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20703-00-00
Spot: NWNE Sec/Twnshp/Rge: 18-24S-14W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HOLDERNESS Well #: 1
County: STAFFORD Total Vertical Depth: 4190 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4040		WITH 2 SX CMT
SURF	8.625	253		WITH 200 SX CMT
PROD	4.5	4189	1800	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/27/2011 8:00 AM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: ALAN WALKER Company: ZENITH DRILLING Phone: (620) 792-9490

Proposed Plugging Method: CIBP @ 4040' & 2 SX CMT. PLUG AT 940' WITH 15 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: NONE
Date/Time Plugging Completed: 07/28/2011 8:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

1ST PLUG SET CIBP @ 4040' & 2 SX CMT. 2ND PLUG (THROUGH CASING) PULL TO 940' & PUMP 15 SX GEL & 50 SX CMT. 3RD PLUG PULL TO 280' & PUMP 50 SX CMT. LOSING MUD. 4TH PLUG PULL TO 40'. PUMP 85 SX CMT. NO CIRCULATION. SDFN. 5TH PLUG RIHWT TAG CMT AT 140'. PUMP 55 SX CMT & FILL 8 5/8" TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4097	4118		

RECEIVED
AUG 08 2011
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
JUL 28 2011
KCC DODGE CITY

Form CP-28
8/17/11