

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22089-00-01

Spot: SESENWSE

Sec/Twnshp/Rge: 31-15S-21W

1530 feet from S Section Line, 1333 feet from E Section Line

Lease Name: HALBLEIB A

Well #: 3

County: TREGO

Total Vertical Depth: 4382 feet

Operator License No.: 5086

Op Name: PINTAIL PETROLEUM, LTD.

Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216	0	135 SX
PROD	4.5	4382	0	250 SX

Well Type: EOR

UIC Docket No: E26350.1

Date/Time to Plug: 08/01/2011 2:00 PM

Plug Co. License No.: 31627

Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: BILLY BRINEY

Company: PINTAIL PETROLEUM, LTD.

Phone: (785) 798-5116

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls.  
DV Tool at 1772' with 400 sxs cement to surface.

Plugging Proposal Received By: MARVIN MILLS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/01/2011 5:15 PM

KCC Agent: MARVIN MILLS

**Actual Plugging Report:**

Ran tubing to 4247' - pumped 100 sxs cement with 200# hulls.  
Pulled tubing to 2822' - pumped 100 sxs cement.  
Pulled tubing to 1750' - circulated with 120 sxs cement.  
Pulled tubing out - squeezed with 80 sxs cement. S.I.P. 250#.  
Tied onto backside - pumped 20 sxs cement. S.I.P. 200#.

**Perfs:**

Top	Bot	Thru	Comments
4306	4320		CHEROKEE 'BASA

Remarks: SWIFT SERVICES-TICEKT #19733.

Plugged through: TBG


RECEIVED

AUG 08 2011

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

8/17/11  
Form CP-2/3

cc to MIC 8/17/11

AUG 03 2011