

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20348-00-00
Spot: SWNENWSE Sec/Twnshp/Rge: 22-10S-25W
2027 feet from S Section Line, 1723 feet from E Section Line
Lease Name: KNOLL A Well #: 2
County: GRAHAM Total Vertical Depth: 4050 feet

Operator License No.: 31120
Op Name: PELICAN HILL OIL & GAS, INC.
Address: 1401 N EL CAMINO REAL SUITE 207
SAN CLEMENTE, CA 92672

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207	0	150 SX
PROD	4.5	4050		125 SXS

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2011 8:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: HAROLD BELLERIVE Company: PELICAN HILL OIL & GAS, INC. Phone: (785) 635-4531

Proposed Ordered 280 sxs 60/40 pozmix - 4% gel - 300# hulls.
Plugging Shoot perfs at 1900' - 1250' - 220'.
Method: Washed down - got to 2047' - hit sucker rods and tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2011 12:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Ran tubing to 2030' - pumped 175 sxs cement - good circulation out casing and the backside.
Shut in the backside - full.
Pulled tubing out - filled down top with 100 sxs cement and 150# hulls.

Remarks: ALLIED CEMENTING COMPANY-TICKET #43464.

Plugged through: TBG


RECEIVED

AUG 08 2011

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

8/17/11

AUG 03 2011